# BUCKHORN BRANCH STREAM RESTORATION

#### OWNER'S/DEVELOPER'S CERTIFICATION

I/We hereby certify that all clearing, grading, construction, and or development will be done pursuant to this plan and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of Natural Resources approved training program for the control of sediment and erosion before beginning the project.

Willing. Wenn	01/27/2025
Signature	Date
WILLIAM WEAVER, PROJECT MANAGER	
Printed Name and Title	

#### DESIGN CERTIFICATION

I hereby certify that this plan has been prepared in accordance with the "2011 Maryland Standards and Specification for Soil Erosion and Sediment Control," Montgomery County Department of Permitting Services Executive Regulations 5-90, 7-02AM and 36-90, and Montgomery County Department of Public Works and Transportation "Storm Drain Design Criteria" dated August 1988.

Transportation otomi brain besign official c	dated Adgust 1900.
und Talley	01/27/2025
Design Engineer Signature	Date
MARY K. TALLEY, PE	52717
Printed Name	Registration Number

#### **CERTIFICATION OF THE QUANTITIES**

I hereby certify that the estimated total amount of excavation and fill as shown on these plans has been computed to 984 cubic yards of excavation, 2,716 cubic yards of fill and the total area to be disturbed as shown on these plans has been determined to be 133,467 square feet.

Signature Date

MARY K. TALLEY, PE 52717

Printed Name and Title Registration Number

#### MICC LITH I

Call "Miss Utility" at 1-800-257-7777, 48 hours prior to the start of work. The excavator must notify all public utility companies with under ground facilities in the area of proposed excavation and have those facilities located by the utility companies prior to commencing excavation. The excavator is responsible for compliance with requirements of Chapter 36A of the Montgomery County Code.

CERTIFICATIONS ON THIS SHEET ARE REQUIRED ON ANY PLAN INVOLVING STORMWATER MANAGEMENT. THE STRUCTURAL CERTIFICATION IS REQUIRED FOR UNDERGROUND STORMWATER MANAGEMENT STRUCTURES WHERE

POURED CONCRETE WALLS ARE TO BE UTILIZED, OR ON ANY OTHER STRUCTURE MCDPS DEEMS APPROPRIATE.

#### **RELATED REQUIRED PERMITS** To be completed by the consultant and placed on the firest sheet of the Sediment Control/Stormwater Management plan set for al projects TYPE OF PERMIT EXPIRATION DATE REQD RESTRICTION DATES MCDPS Floodplain District WATERWAYS/WETLAND(S) NAB-2023-61768 a. Corp of Engineers 6/30/2025 3/1-5/31 Χ 202361768/23-NT-3272 3/1-5/31 1/30/2029 c. MDE Water Quality Certification MDE Dam Saftey Χ \*\*N.P.D.E.S. **NOTICE OF INTENT** FEMA LOMR (Required Post Construction) OTHERS (Please List): MCDPS SEDIMENT CONTROL 291126 Х DISTRICT 406856 MNCPPC - FOREST CONSERVATION PLAN Approval Date MNCPPC - NRI/FSD 420240360 2/5/2024 \*MCDPS PUBLIC RIGHT OF WAY PERMIT (Includes 404351 2/23/2026 Roadside Tree Protection Plan) MDDNR ROASIDE TREE Approval Date 2024-0526


\*A copy of the approved Roadside Tree Protection Plan must be delivered to the Sediment Control Inpsector at the Preconstruction meeting.

\*\*When a Notice of Intent is required, the sediment control permit may not be issued until confirmation of authorization under the MDE's-20-CP permit has been submitted to DPS.

7/12/2024

# MONTGOMERY COUNTY DEPARTMENT OF ENVIRONMENTAL PROTECTION

#### VICINITY MAP



SCALE: 1" = 1.000'

#### **GENERAL NOTES**

- 1. THE CONTRACTOR WILL IMMEDIATELY INFORM THE COUNTY OF ANY DISCREPANCIES FOUND BETWEEN THE PROJECT PLANS AND CONTRACT SPECIFICATIONS.
- FOR CONSTRUCTION, ALL HORIZONTAL CONTROL SHALL BE NAD 83/91 AND VERTICAL CONTROL NAVD 88.
- 3. TYPES OF STORM DRAIN STRUCTURES REFER TO THE 'DESIGN STANDARDS' OF MONTGOMERY COUNTY DEPARTMENT OF TRANSPORTATION, UNLESS OTHERWISE NOTED.
- 4. INFORMATION CONCERNING UNDERGROUND UTILITIES WAS OBTAINED FROM AVAILABLE RECORDS, THE CONTRACTOR MUST DETERMINE THE EXACT LOCATION AND ELEVATIONS OF THE LINES BY DIGGING TEST PITS BY HAND AT ALL UTILITY CROSSINGS WELL IN ADVANCE OF TRENCHING. IF CLEARANCES ARE LESS THAN SHOWN ON THIS PLAN OR SIX (6) INCHES, WHICHEVER IS LESS, THE CONTRACTOR SHALL CONTACT THE COUNTY.
- 5. REPAIRS TO UTILITIES OR PROPERTY DAMAGED AS A RESULT OF THE CONTRACTOR'S NEGLIGENCE OR METHOD OF OPERATION MUST BE MADE AT THE CONTRACTOR'S EXPENSE BEFORE PROCEEDING WITH
- 6. CALL "MISS UTILITY" AT 1-800-257-7777 FOURTY-EIGHT (48) HOURS PRIOR TO BEGINNING EXCAVATION TO DETERMINE THE EXACT LOCATION OF EXISTING UTILITIES.
- 7. CLEARING TO BE LIMITED TO THE "LIMIT OF DISTURBANCE" AS SHOWN ON THE PLANS.
- 8. ALL GRADING SHALL BE DONE IN SUCH A MANNER AS TO PROVIDE POSITIVE DRAINAGE.
- 9. THE CONTRACTOR SHALL OBTAIN A ROADSIDE TREE PERMIT FOR ANY MAINTENANCE, TREATMENT, PLANTING, REMOVAL OR ROOT CUTTING ON TREES WITHIN THE PUBLIC RIGHT-OF-WAY BEFORE STARTING A JOB. PERMIT REQUIREMENTS MAY BE OBTAINED FROM THE DEPARTMENT OF NATURAL RESOURCES MARYLAND FOREST, PARK AND WILDLIFE SERVICE WHOSE TELEPHONE NUMBER IS (301) 854-6060.
- 10. CONTACT THE WASHINGTON SUBURBAN SANITARY COMMISSION SYSTEM MAINTENANCE ENGINEER BEFORE EXCAVATING BENEATH OR IN THE VICINITY OF EXISTING WATER OR SEWER LINES. BACKFILL TO BE DONE UNDER THE SUPERVISION OF W.S.S.C. CALL 301-699-4420.
- 11. CONTACT WASHINGTON GAS DISPATCH OFFICER AT (703) 750-4831 BEFORE EXCAVATING BENEATH OR IN THE VICINITY OF EXISTING GAS MAIN AND SERVICE LATERALS.
- 12. PRIOR TO VEGETATIVE STABILIZATION, ALL DISTURBED AREAS MUST BE TOPSOILED PER THE MONTGOMERY COUNTY "STANDARDS AND SPECIFICATIONS FOR TOPSOIL".
- 13. FOLLOW TREE AND INFRASTRUCTURE PROTECTION MEASURES SPECIFIED UNDER GENERAL NOTES FOR WORK ON M-NCPPC PROPERTY TO ALL RIGHT-OF-WAY AND PRIVATE PROPERTY AFFECTED.

Sheet Number	Sheet Title
1	COVER SHEET
2	GENERAL NOTES
3	SHEET INDEX
4	EXISTING CONDITIONS
5	EXISTING CONDITIONS
6	EXISTING CONDITIONS
7	EXISTING CONDITIONS
8	PROPOSED CONDITIONS
9	PROPOSED CONDITIONS
10	PROPOSED CONDITIONS
11	PROPOSED CONDITIONS
12	PROFILES
13	PROFILES
14	EROSION AND SEDIMENT CONTROL PLAN
15	EROSION AND SEDIMENT CONTROL PLAN
16	EROSION AND SEDIMENT CONTROL PLAN
17	EROSION AND SEDIMENT CONTROL PLAN
18	TREE PROTECTION PLAN
19	DETAILS
20	DETAILS
21	DETAILS
22	DETAILS
23	EROSION AND SEDIMENT CONTROL DETAILS
24	EROSION AND SEDIMENT CONTROL DETAILS
25	EROSION AND SEDIMENT CONTROL DETAILS
26	EROSION AND SEDIMENT CONTROL NOTES
27	EROSION AND SEDIMENT CONTROL NOTES
28	EROSION AND SEDIMENT CONTROL NOTES
29	PLANTING PLAN
30	PLANTING PLAN
31	PLANTING PLAN
32	PLANTING PLAN
33	PLANTING DETAILS
34	PLANTING SCHEDULES

# CLIENT

RES

6958 AVIATION BLVD., SUITE C GLEN BURNIE, MD 21061 301.850.0448

DATE: ISSUES / REVISIONS

DD/MM/YYYY SUBMISSION DESCTRIPTION



The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

BUCKHORN BRANCH STREAM RESTORATION

TITLE:

**COVER SHEET** 

PROJECT NO.: 23006.01

SEAL:

OF MAR

NATIONAL SEAL:

SEAL:

OF MAR

NATIONAL SEAL:

SEAL:

OF MAR

NATIONAL SEAL:

OF MAR

NA

BY: SF/NW CHECK: KT
DWG. NO.:

SCALE: AS SHOWN

OF 34

PROTECTION PLAN

# LEGEND

#### **EXISTING** MAJOR CONTOUR MINOR CONTOUR PROPERTY LINE SANITARY SEWER STORM DRAIN ----- SD -----STREAM CENTERLINE SOIL TYPE BOUNDARY EXISTING 100 YEAR FLOODPLAIN ----- 100YR ------**EXISTING 100 YEAR FLOODPLAIN** \_\_\_\_\_ 25 FB \_\_\_\_ **BUFFER** WETLAND LIMIT 25 FT WETLAND BUFFER WATER OF THE US 75 FT STREAM BUFFER \_\_\_\_\_ SB \_\_\_\_ TREELINE STEEP SLOPES (15% - 24.99%)STEEP SLOPES (GREATER THAN 25%) T-246 TREE WITH CRITICAL ROOT ZONE TRAVERSE POINT STORMDRAIN MANHOLE **SEWER MANHOLE** UTILITY MANHOLE LIGHT POLE **UTILITY POLE GUY WIRE**

#### Docusign Envelope ID: 718680EA-28F9-45DD-B9E5-FB09D6FB41A6

November 7, 2024

Montgomery County Department of Permitting Services Land Development Division 2425 Reedie Drive, 7th Floor Wheaton, MD, 20902

To Whom it May Concern,

I, Donnis Crump, representing Longmead Crossing Community Services Association, hereby authorize HGS LLC (RES) and its subcontractors to access and perform all activities pursuant to the construction of the Buckhorn Branch Stream Restoration Project located on the following parcels:

ADDRESS	LEGAL DESCRIPTION (SUBDIVISION NAME)	SUBDIVISION (SUBDIVISION No.)	LOT	BLOCK	PARCEL	PLAT	LIBER	FOLIO
PARK VISTA DR 0-0000	LONGMEAD	0255		G	0000	16093	00044	09745
BAUGHMAN DR 0-0000	LONGMEAD	0255		G	0000	16092	00044	09745
PLEASANT MEADOW LN 0-0000	LONGMEAD	0255		G	0000	16091	00044	09745
ALPINE MEADOW LN 0- 0000	LONGMEAD	0255		G	0000	16090	00044	09745
PARK VISTA DR 0-0000	LONGMEAD	0255		G	0000	16049	00044	09745
1801 PARK VIST DR SILVER SPRING 20906-000	LONGMEAD	0255		G	0000	16048	00044	09745

Please contact Will Weaver at RES at wweaver@res.us if you require any further information.

#### Longmead Crossing Community Services Association

Down Crus

Donnis Crump, Board President

Mr. William Weaver, RES

Mr. Mike Trumbauer, Biohabitats, Inc.

Ms. Katie Talley, Biohabitats, Inc. Mr. Nathan Wadley, Biohabitats, Inc

# MAJOR CONTOUR MINOR CONTOUR ALIGNMENT PROPOSED 100 YEAR FLOODPLAIN PROPOSED 100 YEAR FLOODPLAIN LIMIT OF DISTURBANCE FL-12 FILTER LOG BLAZE ORANGE FENCE ROOT PRUNING CLAY PLUG

**PROPOSED** 

OUTFALL **STABILIZATION** 




**COBBLE RIFFLE** 

**BOULDER RIFFLE** 


LOG SILL

ROOTWAD





TOE WOOD TREATMENT



LARGE WOODY DEBRIS **BOULDER TOE PROTECTION** 



TREE REMOVAL




TREE PLANKING




STAGING AND STOCKPILING AREA



MULCH ACCESS ROAD




**HEAVY DUTY MAT** MULCH ACCESS




TEMPORARY BRIDGE



STABILIZED CONSTRUCTION **ENTRANCE** 



PUMP AROUND LOCATION FLOW DIVERSION PIPE



SAND BAG DIKES

FILTER BAG

#### SEQUENCE OF CONSTRUCTION

#### PRECONSTRUCTION PHASE

- PRIOR TO CLEARING OF TREES, INSTALLING SEDIMENT CONTROL MEASURES, OR GRADING, A PRECONSTRUCTION MEETING MUST BE CONDUCTED ON-SITE WITH THE MONTGOMERYCOUNTY DEPARTMENT OF PERMITTING SERVICES (MCDPS) SEDIMENT CONTROL INESPECTOR (240)777-0311 (48 HOURS NOTICE), THE MNCPPC, PLANNING DEPARTMENT PLANS ENFORCEMENT INSPECTOR (301)495-4550 (48 HOURS NOTICE), THE OWNERS REPRESENTATIVE. MARYLAND DEPARTMENT OF ENVIRONMENT (MDE), US ARMY CORP OF ENGINEERS (USACE) AND THE SITE ENGINEER IN ORDER FOR THE MEETING TO OCCUR, THE APPLICANT MUST PROVIDE ONE PAPER SET OF APPROVED SEDIMENT CONTROL PLANS TO THE MCDPS SEDIMENT CONTROL INSPECTOR AT THE PRECONSTRUCTION MEETING. ADDITIONALLY A COPY OF THE APPROVED ROADSIDE TREE PROTECTION PLAN MUST BE PRESENT AT THE PRECONSTRUCTION MEETING. IF NO PLANS ARE PROVIDED THE MEETING SHALL NOT OCCUR AND WILL NEED TO BE RESCHEDULED PRIOR TO THE COMMENCING OF WORK.
- CONTRACTOR TO STAKE OUT LIMITS OF DISTURBANCE AS SHOWN ON DESIGN DOCUMENT. THIS IS A DESIGNATED USE CLASS IV STREAM AND WORK SHALL NOT BE CONDUCTING DURING CLOSURE PERIOD FROM MARCH 1 THROUGH MAY 31.
- APPLY ALL TREE PROTECTION MEASURES AS SHOWN ON DESIGN DOCUMENTS.
- AFTER THE PRE-CONSTRUCTION MEETING THE PERMITTEE MUST OBTAIN WRITTEN APPROVAL FROM THE MNCPPC INSPECTOR, CERTIFYING THAT THAT THE LIMITS OF DISTURBANCE AND TREE PROTECTION MEASURES ARE CORRECTLY MARKED AND INSTALLED PRIOR TO COMMENCING ANY CLEARING.
- WITH THREE-DAY CLEAR WEATHER FORECAST, CLEAR AND GRUB FOR INSTALLATION OF CONSTRUCTION SAFETY FENCING, SILT FENCE, FILTER LOG, STABILIZED CONSTRUCTION ENTRANCES, AND MULCH ACCESS ROADS LIMITING EXCESSIVE DISTURBANCE. SEDIMENT CONTROL INSPECTOR TO CONFIRM FILTER BAG PLACEMENT IN FIELD.
- ONCE THE SEDIMENT CONTROL DEVICES ARE INSTALLED, THE PERMITTEE MUST OBTAIN WRITTEN APPROVAL FROM THE MCDPS INSPECTOR BEFORE PROCEEDING WITH ANY ADDITIONAL CLEARING, GRUBBING, OR GRADING.
- SEDIMENT CONTROL DEVICES TO REMAIN IN PLACE UNTIL ALL CLEARING AND GRUBBING AND GRADING COMPLETED AND WRITTEN APPROVAL RECEIVED FROM MCDPS SEDIMENT CONTROL INSPECTOR.

#### CONSTRUCTION PHASE

NOTIFY "MISS-UTLITY" AT 1-800-257-7777 AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION WORK BEING DONE. IN ADDITION, ENGAGE WSSC UTILITY LOCATOR FOR WORK CONDUCTED IN SEWER EASEMENTS.

#### INSTREAM CONSTRUCTION

- 2. CONTRACTOR SHALL COMPLETE STREAM WORK EITHER FROM UPSTREAM TO DOWNSTREAM OR DOWNSTREAM TO UPSTREAM. INSTALL SAND BAGS AND PUMP AROUND PRACTICES FOR ALL PROPOSED INSTREAM WORK. RUN PUMP CONTINUOUSLY DURING WORK HOURS WHEN BASEFLOW IS PRESENT UNTIL THE SITE IS TEMPORARILY STABILIZED. USE FILTER BAGS TO DEWATER THE INSTREAM WORK AREA AS NEEDED DURING CONSTRUCTION.
- AFTER INSTALLATION OF PUMP-AROUND PRACTICES, CLEAR LIMITS OF DISTURBANCE AS REQUIRED TO BEGIN GRADING ACTIVITIES. PUMP ANY FLOW WITHIN THE CHANNEL AROUND WORK EXTENTS DURING INSTREAM WORK.
- CONSTRUCT ALL BED AND BANK TREATMENTS AS OUTLINED IN CONSTRUCTION DETAILS AND PROVIDED SPECIFICATIONS.
- CONTRACTOR SHALL ONLY DISTURB AND BEGIN WORK ON AN AREA WHICH CAN BE COMPLETED BY THE END OF THE DAY. THIS INCLUDES GRADING ADJACENT TO THE CHANNEL. ALL FINISHED GRADING MUST BE PERMANENTLY STABILIZED AT THE END OF EACH DAY WITH SEED AND MULCH OR SEED AND MATTING AS SPECIFIED ON THE PLANS. OTHERWISE TEMPORARILY STABILIZE ALL DISTURBED AREAS AT THE END OF EACH DAY.
- CONTRACTOR SHALL NOT REMOVE SAND BAGS AND PUMP-AROUND PRACTICES AT THE END OF EACH WORKING DAY UNTIL A STABLE CONVEYANCE CAN BE PROVIDED FOR INSTREAM BASEFLOW.
- FOLLOWING STREAM RESTORATION CONSTRUCTION AND WITH APPROVAL OF MCDPS SEDIMENT CONTROL INSPECTOR AND ENGINEER, REMOVE ALL SEDIMENT AND EROSION CONTROL MEASURES NOT REQUIRED FOR OTHER CONSTRUCTION PHASES. EXERCISE CARE TO REMOVE FROM SITE ALL EXCESS CONSTRUCTION DEBRIS AND TRASH GENERATED FROM CONSTRUCTION ACTIVITIES.

#### DEMOBILIZATION

- COMPLETE IN-KIND RESTORATION OF ANY DAMAGE TO EXISTING INFRASTRUCTURE AND GRADE EITHER ON-SITE OR OFF-SITE.
- COMPLETE FINAL PERMANENT VEGETATIVE STABILIZATION OF SITE. ALL PLANTING WORK REQUIRE SAME DAY STABILIZATION.
- 10. WITH APPROVAL OF MCDPS SEDIMENT CONTROL INSPECTOR AND ENGINEER REMOVE REMAINING SEDIMENT CONTROLS AND STABILIZE ANY REMAINING DISTURBED AREAS RESTORING EARTH TO EXISTING GRADES WHERE APPLICABLE.
- 11. PLANT SITE ACCORDING TO PLANTING PLAN IN APPROPRIATE PLANTING SEASON. ALL PLANTING WORK REQUIRES SAME DAY STABILIZATION.

# CLIENT

ISSUES / REVISIONS

SUBMISSION DESCTRIPTION

6958 AVIATION BLVD.. SUITE C GLEN BURNIE, MD 21061 301.850.0448



The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

# **BUCKHORN BRANCH** STREAM RESTORATION

# **GENERAL NOTES**


SCALE: NA


BY: SF/NW


PROJECT NO. : 23006.01


2 OF 34


2/7/2025 I:\Projects\23006.01 Buckhorn Branch Stream Restoration\CAD\Plans\cv01bb.dwg





























CLIENT

RES 6958 AVIATION BLVD., SUITE C GLEN BURNIE, MD 21061 301.850.0448

DATE: ISSUES / REVISIONS

SUBMISSION DESCTRIPTION

The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

BUCKHORN BRANCH STREAM RESTORATION

PROFILES

PROJECT NO.: 23006.01


SEAL:


BY: SF/NW


CHECK


DWG. NO.:

PROSENTE OF MAR PROSENTE OF MA









TREE ID	COMMON NAME	SCIENTIFIC NAME	DBH (INCHES)	CONDITION	STATUS
T1	Red Maple	Acer rubrum	26	Poor	SAVE
T2 T3	Tulip Tree	Liriodendron tulipifera Platanus occidentalis	31 15.5	Fair Good	SAVE SAVE
T4	Sycamore Siberian Elm	Ulmus pumila	13.5	Poor	SAVE
T5	Tulip Tree	Liriodendron tulipifera	33.7	Excellent	SAVE
T6	Black Cherry	Prunus serotina	14.8	Fair	SAVE
T7 T8	Black Cherry	Prunus serotina  Acer rubrum	18 30.1	Poor Fair	SAVE PLANK
T9	Red Maple Red Maple	Acer rubrum  Acer rubrum	22.6	Poor	REMOVAL
T10	Red Maple	Acer rubrum	12.6	Good	SAVE
T11	Red Maple	Acer rubrum	16.1	Good	SAVE
T12	Red Maple	Acer rubrum	11.8	Fair	SAVE
T13 T14	Red Maple American Elm	Acer rubrum Ulmus americana	20.3 15.1	Poor Fair	SAVE PLANK
T15	Sycamore	Platanus occidentalis	29.5	Good	PLANK
T16	Red Maple	Acer rubrum	12.1	Good	SAVE
T17	Red Maple	Acer rubrum	15.8	Good	SAVE
T18 T19	Red Maple	Acer rubrum	14.8 27.4	Excellent Fair	SAVE SAVE
T20	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	15.7	Fair	SAVE
T21	Tulip Tree	Liriodendron tulipifera	16.2	Fair	SAVE
T22	Tulip Tree	Liriodendron tulipifera	14.6	Fair	SAVE
T23	Tulip Tree	Liriodendron tulipifera	25.8	Dead	SAVE
T24	Red Maple	Acer rubrum	15.1	Poor Good	SAVE
T25 T26	Tulip Tree Red Maple	Liriodendron tulipifera  Acer rubrum	11.2 16.1	Poor	SAVE REMOVAL
T27	Tulip Tree	Liriodendron tulipifera	11.8	Good	SAVE
T28	Red Maple	Acer rubrum	18.9	Fair	SAVE
T29	Red Maple	Acer rubrum	11.7	Poor	SAVE
T30 T31	Tulip Tree American Elm	Liriodendron tulipifera Ulmus americana	23.4 16	Good Fair	SAVE PLANK
T32	Tulip Tree	Liriodendron tulipifera	24.5	Fair Fair	REMOVAL
T33	Tulip Tree	Liriodendron tulipifera	33.5	Good	PLANK
T34	Sycamore	Platanus occidentalis	25.9	Excellent	PLANK
T35	Tulip Tree	Liriodendron tulipifera	25.3	Fair	SAVE
T36 T37	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	17.2 29.4	Excellent Good	SAVE SAVE
T38	Tulip Tree	Liriodendron tulipifera	25.2	Good	SAVE
T39	Tulip Tree	Liriodendron tulipifera	24.3	Good	SAVE
T40	American Elm	Ulmus americana	13.8	Good	SAVE
T41	Tulip Tree	Liriodendron tulipifera	23.2	Fair	SAVE
T42 T43	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	23.4 29.8	Fair Excellent	SAVE SAVE
T44	Black Walnut	Juglans nigra	23.8	Fair	PLANK
T45	Tulip Tree	Liriodendron tulipifera	35.1	Good	SAVE
T46	Tulip Tree	Liriodendron tulipifera	23.7	Excellent	SAVE
T47	Tulip Tree	Liriodendron tulipifera	22.5	Fair	SAVE
T48 T49	American Elm Tulip Tree	Ulmus americana Liriodendron tulipifera	16.4 29.3	Good Good	PLANK SAVE
T50	Tulip Tree	Liriodendron tulipifera	26.6	Good	SAVE
T51	Tulip Tree	Liriodendron tulipifera	23.4	Fair	REMOVAL
T52	Red Maple	Acer rubrum	13.9	Good	SAVE
T53	Tulip Tree	Liriodendron tulipifera	27.1	Good	SAVE
T54 T55	Tulip Tree Red Maple	Liriodendron tulipifera  Acer rubrum	28 16	Excellent Good	SAVE SAVE
T56	Red Maple	Acer rubrum	12.5	Good	SAVE
T57	Red Maple	Acer rubrum	14.1	Good	SAVE
T58	Tulip Tree	Liriodendron tulipifera	24.7	Good	SAVE
T59 T60	Tulip Tree Red Maple	Liriodendron tulipifera  Acer rubrum	29.7 16	Excellent Good	SAVE SAVE
T61	Red Maple	Acer rubrum	11.6	Fair	SAVE
T62	Red Maple	Acer rubrum	14.9	Fair	SAVE
T63	Tulip Tree	Liriodendron tulipifera	13.8	Excellent	PLANK
T64 T65	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	28.7	Fair Good	SAVE SAVE
T66	Tulip Tree	Liriodenaron tulipijera Liriodendron tulipijera	23.9	Good	SAVE
T67	Red Maple	Acer rubrum	18	Good	SAVE
T68	Tulip Tree	Liriodendron tulipifera	23.3	Excellent	SAVE
T69	Tulip Tree	Liriodendron tulipifera	15.1	Excellent	SAVE
T70 T71A	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	16.4 28.9	Excellent Good	SAVE SAVE
T71B	Tulip Tree	Liriodendron tulipifera	26.4	Good	SAVE
T72	Tulip Tree	Liriodendron tulipifera	29.9	Fair	SAVE
T73	Tulip Tree	Liriodendron tulipifera	24.1	Excellent	SAVE
T74	Tulip Tree	Liriodendron tulipifera	26.6	Excellent	SAVE
T75 T76	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	13.9 29.8	Fair Good	SAVE SAVE
T77	Tulip Tree	Liriodendron tulipifera	29.3	Fair	SAVE
T78	Tulip Tree	Liriodendron tulipifera	35	Fair	PLANK
T79	Red Maple	Acer rubrum	13.5	Poor	SAVE
T80 T81	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	19.6 18	Good Fair	SAVE SAVE
T82A	Tulip Tree	Liriodenaron tulipijera Liriodenaron tulipijera	29.9	Fair Fair	REMOVAL
T82B	Tulip Tree	Liriodendron tulipifera	13.2	Fair	REMOVAL
T83	Tulip Tree	Liriodendron tulipifera	27.7	Good	SAVE
T84	Tulip Tree	Liriodendron tulipifera	18.9	Excellent	SAVE
T85	Tulip Tree	Liriodendron tulipifera	18	Excellent	SAVE
T86 T87	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	21.2 17.3	Good Good	SAVE SAVE
T88	Tulip Tree	Liriodendron tulipifera	15.7	Fair	SAVE
T89	Tulip Tree	Liriodendron tulipifera	14.4	Good	SAVE
T90	Tulip Tree	Liriodendron tulipifera	30.1	Fair	REMOVAL
T91	Tulip Tree	Liriodendron tulipifera	27	Good Fair	SAVE SAVE
T92 T93	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	30.8	Fair Good	SAVE SAVE
T94	Red Maple	Acer rubrum	17.3	Fair	SAVE

DITION	STATUS	TREE ID	COMMON NAME	SCIENTIFIC NAME	DBH (INCHES)	CONDITION	STATUS	TREE ID	COMMON NAME	SCIENTIFIC NAME	DBH (INCHES)	CONDITION	STATUS	TREE ID	COMMON NAME	SCIENTIFIC NAME	DBH (INCHES)	CONDITION
oor	SAVE SAVE	T97A T97B	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	24.9 20.2	Fair Fair	SAVE SAVE	T176 T177	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	31.3 33	Excellent Excellent	SAVE SAVE	T263 T264	Tulip Tree American Elm	Liriodendron tulipifera Ulmus americana	11.8 21.7	Fair Fair
ood	SAVE	T98	Tulip Tree	Liriodendron tulipifera	11.5	Fair	SAVE	T177	Red Maple	Acer rubrum	29.1	Good	SAVE	T265	American Elm	Ulmus americana	23.5	Fair
oor ellent	SAVE SAVE	T99 T100	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	23.1 23.6	Fair Good	SAVE SAVE	T179 T180	Pin Oak Tulip Tree	Quercus palustris Liriodendron tulipifera	39.3 24.2	Fair Fair	SAVE SAVE	T266 T267	Tulip Tree Red Maple	Liriodendron tulipifera  Acer rubrum	11.3 28.2	Good Poor
air	SAVE	T100	Tulip Tree	Liriodendron tulipifera	22.8	Fair	SAVE	T181	Tulip Tree	Liriodendron tulipifera	24.2	Good	SAVE	T268	Sycamore	Platanus occidentalis	25	Poor
oor	SAVE PLANK	T102 T103	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	17.8 32.4	Good Poor	SAVE SAVE	T182 T183	Tulip Tree Pin Oak	Liriodendron tulipifera Quercus palustris	27 26.8	Poor Fair	SAVE SAVE	T269 T270	Tulip Tree Red Maple	Liriodendron tulipifera  Acer rubrum	20.7 15.4	Good Poor
oor	REMOVAL	T103	Tulip Tree	Liriodendron tulipifera	16.8	Fair	SAVE	T184	American Elm	Ulmus americana	27	Good	SAVE	T271	Tulip Tree	Liriodendron tulipifera	46.2	Poor
ood	SAVE SAVE	T105 T106	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	24.5 12.9	Good Poor	SAVE SAVE	T185 T186	Pin Oak Red Maple	Quercus palustris Acer rubrum	24.7 13.7	Good Good	SAVE SAVE	T272 T273	Tulip Tree Black Walnut	Liriodendron tulipifera  Juglans nigra	11.3 19.4	Fair Poor
air	SAVE	T100	Red Maple	Acer rubrum	11.3	Poor	SAVE	T187	Red Maple	Acer rubrum	14.1	Good	SAVE	T274	Tulip Tree	Liriodendron tulipifera	22.5	Fair
oor	SAVE PLANK	T108 T109	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	12.9 14.8	Good Fair	SAVE SAVE	T188 T189	Red Maple Red Maple	Acer rubrum Acer rubrum	13.5 27	Fair Fair	SAVE SAVE	T275 T276	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	14.2	Poor Poor
ood	PLANK	T110	Tulip Tree	Liriodendron tulipifera	24.5	Good	SAVE	T190	Red Maple	Acer rubrum	25.4	Good	SAVE	T277	Tulip Tree	Liriodendron tulipifera	23	Fair
ood	SAVE SAVE	T111 T112	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	25.5 20.2	Good Good	SAVE SAVE	T191 T192	Tulip Tree Red Maple	Liriodendron tulipifera Acer rubrum	24.7	Poor Fair	SAVE SAVE	T278 T279	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	13.3	Fair Poor
ellent	SAVE	T113	Red Maple	Acer rubrum	13.2	Poor	SAVE	T200	Sugar Maple	Acer saccharum	32.5	Fair	SAVE	T280	Tulip Tree	Liriodendron tulipifera	20.4	Good
air air	SAVE SAVE	T114 T115	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	20.2	Poor Poor	PLANK SAVE	T201 T202	River Birch Walnut	Betula nigra Juglans nigra	9	Good Poor	SAVE SAVE	T281	Tulip Tree	Liriodendron tulipifera	15.8 17	Poor Poor
air	SAVE	T116A	Tulip Tree	Liriodendron tulipifera	19.5	Fair	PLANK	T203	River Birch	Betula nigra	11.5	Good	SAVE		· 	, .	13	Poor
air ead	SAVE SAVE	T116B T117	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	19.5 27	Fair Fair	PLANK REMOVAL	T204	Walnut	Juglans nigra	11.5	Good Dead	SAVE SAVE	T282 T283	Black Walnut Tulip Tree	Juglans nigra Liriodendron tulipifera	16.4 14.2	Poor Poor
oor	SAVE	T118	Tulip Tree	Liriodendron tulipifera	22.5	Fair	REMOVAL	T205	Tulip Tree	Liriodendron tulipifera	18	Poor	SAVE	T284	Tulip Tree	Liriodendron tulipifera	11.1	Poor
ood oor	SAVE REMOVAL	T119 T120	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	24.2 16.1	Fair Good	REMOVAL PLANK	T206 T207	Walnut American Elm	Juglans nigra Ulmus americana	12.5 10.5	Poor Fair	SAVE SAVE	T285 T286	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	33 15.8	Poor Poor
ood	SAVE	T121	Tulip Tree	Liriodendron tulipifera	16.5	Fair	SAVE	T208	Sycamore	Platanus occidentalis	10.5	Good	SAVE	T287	Tulip Tree	Liriodendron tulipifera	32.4	Poor
air oor	SAVE SAVE	T122 T123	Tulip Tree Black Cherry	Liriodendron tulipifera Prunus serotina	16.8 14.9	Poor Good	SAVE SAVE	T209 T210	Black Willow Northern Catalpa	Salix nigra Catalpa speciosa	25.2 23.5	Poor Poor	SAVE SAVE	T288 T289	Black Walnut Tulip Tree	Juglans nigra Liriodendron tulipifera	18.2 20.8	Poor Poor
ood	SAVE	T124	Tulip Tree	Liriodendron tulipifera	20.9	Good	SAVE	T211	Red Maple	Acer rubrum	15	Fair	SAVE	T290	Tulip Tree	Liriodendron tulipifera	22.5	Poor
air air	PLANK REMOVAL	T125 T126	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	20.5 24.5	Good Good	SAVE PLANK	T212 T213	Red Maple Red Maple	Acer rubrum Acer rubrum	11 14.7	Fair Poor	SAVE SAVE	T291 T292	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	17.7 12.6	Fair Fair
ood	PLANK	T127	Tulip Tree	Liriodendron tulipifera	23.9	Good	SAVE	T214	Black Walnut	Juglans nigra	24	Fair	SAVE	T293	Tulip Tree	Liriodendron tulipifera	14.1	Fair
ellent air	PLANK SAVE	T128 T129	American Beech Pignut Hickory	Fagus grandifolia Carya glabra	14.4 28.4	Excellent Excellent	SAVE SAVE	T215 T216	Red Maple Black Walnut	Acer rubrum Juglans nigra	17.4 21	Poor Poor	SAVE SAVE	T294	Tulip Tree	Liriodendron tulipifera	12.9 17.6	Fair Poor
ellent	SAVE	T130	Tulip Tree	Liriodendron tulipifera	40	Good	PLANK	T217	Juniper	Juniperus communis	25	Poor	REMOVAL	T295	Tulip Tree	Liriodendron tulipifera	16.9	Fair
ood	SAVE SAVE	T131 T132	Tulip Tree Pignut Hickory	Liriodendron tulipifera Carya glabra	13.4 16.5	Good Fair	SAVE SAVE	T218 T219	Juniper Juniper	Juniperus communis Juniperus communis	22.9 18.9	Fair Good	REMOVAL REMOVAL	T296 T297	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	12.1 28.3	Fair Poor
ood	SAVE	T133	Tulip Tree	Liriodendron tulipifera	30.6	Excellent	SAVE	T220	Juniper	Juniperus communis	14.2	Good	REMOVAL	T298	Tulip Tree	Liriodendron tulipifera	27.3	Poor
ood air	SAVE SAVE	T134 T135	Red Maple Red Maple	Acer rubrum Acer rubrum	21.1 17.7	Fair Fair	REMOVAL SAVE	T221 T222	Black Walnut Juniper	Juglans nigra Juniperus communis	17 12	Poor Fair	REMOVAL REMOVAL	T299 T300	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	26.6 18.8	Poor Fair
air	SAVE	T136	Pignut Hickory	Carya glabra	17.7	Good	SAVE	T223	Black Cherry	Prunus serotina	20.4	Good	REMOVAL	T301	Tulip Tree	Liriodendron tulipifera	29.9	Fair
ellent air	SAVE PLANK	T137A T137B	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	30 22.6	Fair Fair	SAVE SAVE	T224 T225	Juniper Juniper	Juniperus communis Juniperus communis	14.1	Poor Fair	REMOVAL REMOVAL	T302	Tulip Tree  Eastern Red Cedar	Liriodendron tulipifera	26 11.6	Poor Poor
ood	SAVE	T138	Tulip Tree	Liriodendron tulipifera	18.6	Poor	SAVE	T226	Sycamore	Platanus occidentalis	17.3	Excellent	SAVE	T304	Black Walnut	Juniperus virginiana	13.8	Poor Poor
ellent air	SAVE SAVE	T139 T140	Tulip Tree Red Maple	Liriodendron tulipifera Acer rubrum	15.3 24	Fair Poor	SAVE SAVE	T227 T228	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	15.5 15.3	Good Good	SAVE SAVE	T305	Tulip Tree	Juglans nigra Liriodendron tulipifera	33.9	Poor
ood	PLANK	T141	Pignut Hickory	Carya glabra	11.9	Good	SAVE	T229	Tulip Tree	Liriodendron tulipifera	25	Fair	PLANK	T306	Tulip Tree	Liriodendron tulipifera	23.5	Poor Poor
ood	SAVE SAVE	T142 T143	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	39.5 25.8	Good Good	SAVE SAVE	T230 T231	Tulip Tree Walnut	Liriodendron tulipifera Juglans nigra	16.3 17	Poor Fair	REMOVAL REMOVAL	T307	Black Walnut	Juglans nigra	17.8	Poor
air	REMOVAL	T144	Tulip Tree	Liriodendron tulipifera	27.3	Good	SAVE	T232	Tulip Tree	Liriodendron tulipifera	11	Good	SAVE	T308 T309	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	29.8 28.8	Fair Good
ood	SAVE SAVE	T145 T146	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	25.5 26.2	Good Good	SAVE SAVE	T233 T234	Sycamore Tulip Tree	Platanus occidentalis Liriodendron tulipifera	37.5 15.8	Good Poor	PLANK SAVE	T310	Tulip Tree	Liriodendron tulipifera	18.4	Fair
ellent	SAVE	T147	Northern Red Oak	Quercus rubra	25.4	Good	SAVE	T235	Tulip Tree	Liriodendron tulipifera	17.7	Good	REMOVAL	T311 T312	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	13.6 37.8	Fair Poor
ood	SAVE SAVE	T148 T149	Tulip Tree Northern Red Oak	Liriodendron tulipifera Quercus rubra	25.2 26.9	Excellent Poor	SAVE SAVE	T236 T237	Beech Red Maple	Fagus grandifolia Acer rubrum	30	Fair Poor	REMOVAL REMOVAL	T313	Tulip Tree	Liriodendron tulipifera	27.1	Fair
ood	SAVE SAVE	T150	Northern Red Oak	Quercus rubra	26.3	Excellent	SAVE	T238 T239	Red Maple Black Gum	Acer rubrum	11.4	Poor	REMOVAL REMOVAL	T314 T315	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	32 17.1	Fair Fair
ood ellent	SAVE	T151A T151B	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	27.9 35.3	Fair Fair	SAVE SAVE	T240	Walnut	Nyssa sylvatica Juglans nigra	18.5 12.5	Poor Fair	PLANK	T316	Tulip Tree	Liriodendron tulipifera	39.4	Fair
ood air	SAVE SAVE	T152 T153	Tulip Tree Tulip Tree	Liriodendron tulipifera	29.2 25.2	Good Poor	SAVE SAVE	T241	Red Maple	Acer rubrum	21.8 14.6	Poor Poor	PLANK PLANK	T317 T318	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	13.2 13.2	Fair Poor
air	SAVE	T154	Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	24.3	Fair	SAVE	T242	Tulip Tree	Liriodendron tulipifera	34.4	Fair	PLANK	T319	Tulip Tree	Liriodendron tulipifera	14	Poor
ellent air	PLANK SAVE	T155 T156	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	26.4 26.1	Good Fair	SAVE SAVE	T243 T244	Walnut Tulip Tree	Juglans nigra Liriodendron tulipifera	28 19.1	Fair Good	SAVE PLANK	T320 T321	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	31.1	Poor Fair
ood	SAVE	T157	Tulip Tree Tulip Tree	Liriodendron tulipifera	26.1	Poor	SAVE	T245	Tulip Tree	Liriodendron tulipifera	18.6	Good	REMOVAL	T322	Tulip Tree	Liriodendron tulipifera	21.2	Fair
ood	SAVE SAVE	T158 T159	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	32.8 26.6	Excellent Fair	SAVE SAVE	T246 T247	Sycamore Tulip Tree	Platanus occidentalis Liriodendron tulipifera	39.1 48.1	Fair Fair	SAVE PLANK	T323	Black Walnut	Juglans nigra	21.1 30	Poor Fair
ellent	SAVE	T160	Tulip Tree	Liriodendron tulipifera	34.7	Poor	SAVE	T248	Red Maple	Acer rubrum	10	Poor	SAVE	T324	Tulip Tree	Liriodendron tulipifera	13	Fair
ellent ellent	SAVE SAVE	T161 T162	Tulip Tree Pin Oak	Liriodendron tulipifera  Quercus palustris	30.7 31.5	Good Fair	SAVE SAVE	T249 T250	Red Maple Red Maple	Acer rubrum Acer rubrum	9 20.8	Poor Good	SAVE SAVE				26.3 23.7	Fair Fair
ood	SAVE	T163	Red Maple	Acer rubrum	26.7	Good	SAVE	T251	Sycamore	Platanus occidentalis	24.3	Fair	PLANK	T325	Tulip Tree	Liriodendron tulipifera	36.9	Poor
ood air	SAVE SAVE	T164 T165	Tulip Tree Red Maple	Liriodendron tulipifera Acer rubrum	27.1 30.4	Excellent Good	SAVE SAVE	T252 T253	White Ash Tulip Tree	Fraxinus americana Liriodendron tulipifera	16.8 19	Poor Good	SAVE SAVE	T326 T327	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	31 15.7	Poor Poor
ellent	SAVE	T166	Red Maple	Acer rubrum	37.9	Good	SAVE	T254	Tulip Tree	Liriodendron tulipifera	11.5	Good	SAVE	T328	Tulip Tree	Liriodendron tulipifera	31.8	Poor
ellent air	SAVE SAVE	T167 T168	Pin Oak Red Maple	Quercus palustris Acer rubrum	24.5 32.2	Good Good	SAVE SAVE	T255 T256	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	19	Good Poor	SAVE REMOVAL	T329	tulip poplar	Liriodendron tulipifera	35.3 15.3	Fair
ood	SAVE	T169	American Sycamore	Platanus occidentalis	37.5	Excellent	SAVE	T257	Hop-Hornbeam	Ostrya virginiana	20.3	Fair	PLANK	T330	tulip poplar	Liriodendron tulipifera	14	Good
air air	SAVE PLANK	T170 T171A	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	31.1 36.5	Excellent Good	SAVE SAVE	T258 T259	Sycamore Sycamore	Platanus occidentalis Platanus occidentalis	39 42	Fair Fair	PLANK PLANK	T331 T332	black locust sycamore	Robinia pseudoacacia Platanus occidentalis	12.6 17	Fair Fair
oor	SAVE	T171B	Tulip Tree	Liriodendron tulipifera	24.3	Good	SAVE	T260	American Elm	Ulmus americana	13	Fair	PLANK	T333	tulip poplar	Liriodendron tulipifera	14.5	Good
ood air	SAVE SAVE	T172A T172B	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	28.4 12.1	Good Good	SAVE SAVE				29.6 14.1	Fair Fair	SAVE SAVE	T334 T335	tulip poplar tulip poplar	Liriodendron tulipifera Liriodendron tulipifera	16.8 13.3	Good Dead
air	REMOVAL	T172C	Tulip Tree	Liriodendron tulipifera	13.9	Good	SAVE	T261	Sycamore	Platanus occidentalis	21.3	Fair	SAVE	T336	black walnut	Juglans nigra	13.1	Good
air ood	REMOVAL SAVE	T173 T174	Tulip Tree Tulip Tree	Liriodendron tulipifera Liriodendron tulipifera	29.4 22.3	Poor Good	SAVE SAVE				30.5	Fair Fair	SAVE SAVE	T337 T340	black walnut pin oak	Juglans nigra Quercus palustris	11.7 32	Fair Good
ellent	SAVE	T175	Tulip Tree	Liriodendron tulipifera	29	Excellent	SAVE	T3.03	C	Distance - ' ' '	28.2	Good	SAVE	T341	northern catalpa	Catalpa speciosa	33 14.6	Good
ellent ood	SAVE SAVE							T262	Sycamore	Platanus occidentalis	23 22.7	Good Good	SAVE SAVE	R2 R3	Tulip tree Tulip tree	Liriodendron tulipifera Liriodendron tulipifera	14.6	Fair Fair
ood	SAVE													R4 R5	Tulip tree Arborvitae	Liriodendron tulipifera Thuja occidentalis	10.4	Fair Good
air ood	SAVE SAVE													R6	Arborvitae	Thuja occidentalis Thuja occidentalis	1	Good
air	REMOVAL													R7 R8	Arborvitae Arborvitae	Thuja occidentalis Thuja occidentalis	1 1	Good Good
ood air	SAVE SAVE													R8 R9	Arborvitae Arborvitae	Thuja occidentalis Thuja occidentalis	1	Good
ood	SAVE													R10 R11	Redbud Red Maple	Cercis canadensis Acer rubrum	9.1 8.4	Good Fair
air air	SAVE PLANK													R12	Sycamore	Platanus occidentalis	17.4	Good
or	PLANK																	

# CLIENT

6958 AVIATION BLVD., SUITE C GLEN BURNIE, MD 21061 301.850.0448

STATUS

SAVE

SAVE SAVE

SAVE

REMOVAL REMOVAL SAVE REMOVAL REMOVAL SAVE SAVE SAVE SAVE SAVE SAVE REMOVAL SAVE SAVE REMOVAL REMOVAL

REMOVAL

SAVE REMOVAL SAVE PLANK SAVE SAVE SAVE SAVE SAVE SAVE PLANK PLANK PLANK PLANK SAVE SAVE REMOVAL REMOVAL REMOVAL REMOVAL PLANK SAVE SAVE SAVE SAVE SAVE SAVE SAVE PLANK PLANK SAVE SAVE SAVE SAVE SAVE PLANK SAVE PLANK PLANK REMOVAL

SAVE REMOVAL REMOVAL SAVE

SAVE SAVE

SAVE SAVE

SAVE

REMOVAL REMOVAL

SAVE REMOVAL

REMOVAL
REMOVAL
REMOVAL
PLANK
SAVE
SAVE
REMOVAL

SAVE REMOVAL

SAVE SAVE SAVE

SAVE SAVE

SAVE SAVE SAVE REMOVAL REMOVAL

> SAVE SAVE

DATE: ISSUES / REVISIONS

DD/MM/YYYY SUBMISSION DESCTRIPTION



The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

# BUCKHORN BRANCH STREAM RESTORATION

TITLE:

# TREE PROTECTION PLAN


PROJECT NO.: 23006.01

SEAL:

BY: SF/NW

DWG. NO.:

SCALE: NTS



CLIENT

6958 AVIATION BLVD.. SUITE C GLEN BURNIE, MD 21061 301.850.0448

ISSUES / REVISIONS SUBMISSION DESCTRIPTION



The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

# **BUCKHORN BRANCH** STREAM RESTORATION

**DETAILS** 

PROJECT NO.: 23006.01 OF MARY

SCALE: NTS BY: SF/NW DWG. NO.:

		RIFFLF	STRUCTURE TA	BLE	
ID	Station	Node	Easting	Northing	Elevation
		US-L	1299485.7972'	523278.3456'	340.2
		US-T US-R	1299483.8372' 1299481.8772'	523272.1343' 523265.9230'	339.0 340.2
B-1	2+37.8	DS-R	1299481.8772	523273.3259	340.2
		DS-T	1299503.3290'	523265.9760'	338.4
		DS-R	1299501.0063'	523258.6261'	340.0
		US-L	1299530.0464'	523244.7156'	339.7
		US-T	1299523.6884'	523243.4078'	338.4
C-1	2+90.1	US-R	1299517.2702'	523242.0875'	339.7
		DS-L DS-T	1299535.3207' 1299527.9290'	523224.3127' 523222.7920'	339.5 338.0
		DS-R	1299527.9290	523221.2833'	339.5
		US-L	1299550.2140'	523195.7896'	339.2
		US-T	1299545.7595'	523191.0190'	338.0
C-2	3+48.1	US-R	1299541.3078'	523186.2471'	339.2
0 2	3. 10.1	DS-L	1299564.8876'	523183.8301'	339.0
		DS-T	1299559.5631'	523178.1359'	337.4
		DS-R	1299554.2264'	523172.4288'	339.0
		US-L US-T	1299600.5135' 1299600.5140'	523175.2414' 523168.6901'	338.6 337.4
		US-R	1299600.5144	523162.1387'	338.6
C-3	4+10.4	DS-L	1299624.5164'	523176.3129'	338.3
		DS-T	1299624.5157'	523168.7317'	336.7
		DS-R	1299624.5150'	523161.1501'	338.3
		US-L	1299653.7615'	523164.8728'	337.9
		US-T	1299649.6734'	523159.8234'	336.7
B-2	4+61.6	US-R	1299645.5853'	523154.7740'	337.9
		DS-L	1299670.1013' 1299665.2190'	523153.2841' 523147.2475'	337.7 336.1
		DS-T DS-R	1299665.2190	523147.2475	336.1
		US-L	1299000.5506	523141.2108	337.7
		US-T	1299710.7349'	523114.0463'	336.1
B-3	5+38.1	US-R	1299707.8774'	523108.1965'	337.3
D-3	J+36.1	DS-L	1299729.8473'	523113.1478'	337.1
		DS-T	1299726.5178'	523106.3290'	335.6
		DS-R	1299723.1831'	523099.4995'	337.1
		US-L	1299752.9755'	523090.5978'	336.8
	5+84.3	US-T US-R	1299747.3881' 1299741.7996'	523087.2274' 523083.8563'	335.6 336.8
C-4		DS-L	1299761.5282'	523077.9323'	336.6
		DS-T	1299755.2716'	523074.1760'	335.1
		DS-R	1299749.0151'	523070.4198'	336.6
	6+25.0	US-L	1299776.6910'	523064.6986'	336.3
		US-T	1299774.8374'	523058.7551'	335.1
C-5		US-R	1299772.9942'	523052.8450'	336.3
		DS-L	1299796.2440'	523060.2242'	336.2
			DS-T DS-R	1299793.9224' 1299791.6007'	523052.7854' 523045.3466'
		US-L	1299865.1915'	523069.6386'	335.8
		US-T	1299864.2033'	523063.1573'	334.6
<b>C C</b>	7+19.4	US-R	1299863.2131'	523056.6629'	335.8
C-6		DS-L	1299882.3558'	523068.0250'	335.6
		DS-T	1299881.2481'	523060.6380'	334.0
		DS-R	1299880.1404'	523053.2509'	335.6
		US-L	1299907.1846'	523052.9333'	335.2
		US-T	1299902.4702' 1299897.8134'	523048.8896' 523044.8077'	334.0
B-4	7+62.7	US-R DS-L	1299897.8134	523038.7011'	335.2 335.0
		DS-T	1299915.7278'	523033.7611	333.4
		DS-R	1299909.7977'	523028.4095'	335.0
		US-L	1299963.8229'	523018.9261'	334.6
		US-T	1299962.0051'	523012.5276'	333.4
C-7	8+34.6	US-R	1299960.1873'	523006.1292'	334.6
		DS-L	1299983.2011'	523014.0941'	334.3
		DS-T	1299981.1128'	523007.0114'	332.8
		DS-R	1299979.0245'	522999.9286'	334.3
		US-L US-T	1300010.9641' 1300007.0730'	522999.6442' 522994.2606'	334.0 332.8
		US-R	1300007.0730	522989.0053'	334.0
C-8	8+83.6	DS-L	1300032.4951'	522985.9408'	333.6
		DS-T	1300027.7767'	522979.3535'	331.9
		DS-R	1300023.0582'	522972.7661'	333.6
		US-L	1300054.8162'	522961.7976'	331.1
		US-T	1300049.5001'	522957.8471'	331.9
C-9	9+39.8	US-R	1300044.1839'	522953.8966'	331.1
~		DS-L	1300065.6439'	522948.9636'	332.8
		DS-T	1300059.4839'	522944.3927'	331.3
		DS-R	1300053.3336'	522939.8257'	332.8
		US-L	1300080.8305' 1300080.0341'	522939.1754' 522932.4805'	332.5 331.3
		US-T US-R	1300080.0341	522932.4805	331.3 332.5
C-10	9+81.0	DS-R	1300079.2382	522925.7891	331.9
		DS-T	1300110.1803	522937.2179	330.3
		DS-R	1300103.2377	522920.8134'	331.9
		US-L	1300139.8575'	522917.1087'	331.5
		US-T	1300134.2969'	522913.4542'	330.3
C-11	10+40 0	US-R	1300128.7363'	522909.7997'	331.5
C-11	10+40.9	US-R DS-L	1300128.7363' 1300151.9652'	522909.7997' 522900.7590'	331.5

ID	Station	Node	Easting	Northing	Elevation
		US-L	1300168.5363'	522891.9359'	330.4
		US-T	1300169.2775'	522885.3733'	329.2
C-12	10+88.8	US-R	1300170.0373'	522878.8028'	330.4
C-12	10+00.0	DS-L	1300189.8758'	522895.6577'	330.3
		DS-T	1300190.7543'	522887.8700'	328.7
		DS-R	1300191.6653'	522880.0586'	330.3
		US-L	1300255.1563'	522918.8014'	329.9
		US-T	1300253.0391'	522912.5145'	328.7
C-13	11+80.7	US-R	1300250.9115'	522906.1936'	329.9
C-13	11+60.7	DS-L	1300279.2758'	522912.0885'	329.5
		DS-T	1300276.7445'	522904.5334'	327.9
		DS-R	1300274.2179'	522896.9925'	329.5
		US-L	1300335.8132'	522901.4124'	329.1
		US-T	1300338.0317'	522895.1530'	327.9
C-14	12+69.2	US-R	1300340.2795'	522888.8107'	329.1
C 14	12105.2	DS-L	1300356.5554'	522910.0904'	328.8
		DS-T	1300359.1836'	522902.6794'	327.3
		DS-R	1300361.8118'	522895.2684'	328.8
		US-L	1300386.9245'	522909.4109'	328.5
		US-T	1300384.8584'	522903.0168'	327.3
C-15	13+17.8	US-R	1300382.8182'	522896.7032'	328.5
C 13	13.17.0	DS-L	1300404.4788'	522904.7686'	328.2
		DS-T	1300402.1104'	522897.4434'	326.7
		DS-R	1300399.7419'	522890.1182'	328.2
		US-L	1300427.1285'	522899.7652'	327.9
		US-T	1300426.9168'	522893.1273'	326.7
B-5	13+61.2	US-R	1300426.7071'	522886.5506'	327.9
		DS-L	1300446.3809'	522900.2799'	327.7
		DS-T	1300446.1331'	522892.5150'	326.2
		DS-R	1300445.8853'	522884.7502'	327.7
		US-L	1300476.3167'	522895.0715'	327.4
		US-T	1300474.7486'	522888.6211'	326.2
B-6	14+09.4	US-R	1300473.1891'	522882.2064'	327.4
		DS-L	1300501.7411'	522890.3910'	326.9
		DS-T	1300499.8331'	522882.5390'	325.3
		DS-R	1300497.9251'	522874.6869'	326.9
		US-L	1300532.8465'	522872.9872'	326.5
		US-T	1300528.5382'	522867.9029'	325.3
B-7	14+67.7	US-R	1300524.2298'	522862.8185'	326.5
		DS-L	1300547.0038'	522862.0272'	326.3
		DS-T	1300542.2044'	522856.3632'	324.7
		DS-R	1300537.4049'	522850.6992'	326.3
		US-L	1300569.1376'	522845.5574'	325.9
		US-T	1300567.0421'	522840.1246'	324.7
B-8	15+15.4	US-R	1300564.9465'	522834.6918'	325.9
		DS-L	1300586.6803'	522839.6330'	325.5
		DS-T	1300584.3691'	522833.4500'	323.9
		DS-R	1300582.0579'	522827.2670'	325.5
		US-L	1300611.4180'	522833.6663'	325.1
		US-T	1300610.4480'	522827.0887'	323.9
C-16	15+60.8	US-R	1300609.4782'	522820.5116'	325.1
		DS-L	1300633.4421'	522832.2309'	324.8
		DS-T	1300632.2076'	522823.8160'	323.2
		DS-R	1300631.0706'	522816.0653'	324.8
		US-L	1300664.2593'	522837.8609'	324.4
		US-T	1300668.1608'	522832.5186'	323.2
B-9	16+20.5	US-R	1300672.0623'	522827.1762'	324.4
		DS-L	1300681.5327'	522853.0664'	323.0
		DS-T	1300686.3662'	522846.4524'	321.3
		DS-R	1300691.1997'	522839.8383'	323.0



RES

6958 AVIATION BLVD., SUITE C GLEN BURNIE, MD 21061 301.850.0448

DATE: ISSUES / REVISIONS

DD/MM/YYYY SUBMISSION DESCTRIPTION



The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

# BUCKHORN BRANCH STREAM RESTORATION

TITLE

# **DETAILS**

PROJECT NO.: 23006.01

SEAL:

OF MAR


PROJECT NO.: 23006.01

8006.01 SCALE: NTS

BY: SF/NW CHECK: KT


20 OF 34


2/7/2025 I:\Projects\23006.01 Buckhorn Branch Stream Restoration\CAD\Plans\dt01bb.dwg



**PLAN VIEW** 


- 1. SILL SHALL TIE BACK INTO VALLEY SLOPE AND RIFFLE 1' MINIMUM SILLS SHALL BE FIELD LOCATED TO AVOID SIGNIFICANT IMPACTS TO EXISTING ROOT STRUCTURES. A SILL SHALL BE INSTALLED
- APPROXIMATELY EVERY 4' IN VERTICAL DROP ALONG VALLEY SLOPE, AT DIRECTION OF ENGINEER.
- INSTALLATION OF SILLS SHALL INCLUDE MINIMAL EXCAVATION. AND SHALL BE PUSHED BELOW GRADE WHERE POSSIBLE
- JOINTS BETWEEN 2 ABUTTING LOGS SHALL BE STAGGERED SO THAT THEY ARE NO CLOSER THAN 2' FROM JOINTS ON SECOND ROW
- LOG SILL SHALL SLOPE FROM TOE OF VALLLEY SLOPE TO EDGE OF RIFFLE FOLLOWING SLOPE OF EXISTING GROUND.
- 6. LIVE POSTS SHALL BE INSTALLED EVERY 20' MAX SPACING, NOT LOCATED AT JOINT BETWEEN 2 LOGS.






NOT TO SCALE

NOT TO SCALE




2. VERTICAL QUANTITY OF BOULDERS WILL VARY TO MEET ELEVATIONS AND ACHIEVE WALL HEIGHT.



**CROSS SECTION** — INVERTED ROOT WAD OR LWD The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 POOL WSE fx: 410.554.0168 / www.biohabitats.com

NOT TO SCALE


NOT TO SCALE



# STANDING ROOT WAD IN POOL CROSS SECTION, TYP.

**BOULDER TOE** 

- INSTALL IN-STREAM LARGE WOODY DEBRIS OR ROOTWADS AT LOCATIONS SHOWN ON PLAN. PARTIALLY BURY ONSITE LWD OR ROOTWADS INTO THE POOL BOTTOM APPROXIMATELY  $\frac{2}{3}$  OF TOTAL LENGTH TO SECURE IN PLACE AS DIRECTED BY THE ENGINEER.
- EMBED ROOTWADS AT APPROXIMATE CENTER OF CHANNEL OR WHERE CHANNEL IS DEEPEST. 3. IF DOWNED LOG IS BEING USED INSTEAD OF LWD, THE ROOTWAD SHALL BE PLACED WHERE BRANCHES ARE INDICATED ON THIS SHEET.



BOULDER TOE DIMENSIONS (FT)								
A-AXIS	C-AXIS							
2 - 3	1.5 - 2.5	1.5 - 2 .5						



CLIENT

ISSUES / REVISIONS

SUBMISSION DESCTRIPTION

Restore the Earth & Inspire Ecological Stewardship

# **BUCKHORN BRANCH** STREAM RESTORATION





23006.01


21 OF 34


SCALE: NTS

BY: SF/NW









- ROOTWAD

NOT TO SCALE

- COMMON BORROW

BASE

TOE WOOD TREATMENT

PLAN VIEW - CUT AWAY



CLIENT

ISSUES / REVISIONS

SUBMISSION DESCTRIPTION

6958 AVIATION BLVD., SUITE C

GLEN BURNIE, MD 21061

301.850.0448

The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

# BUCKHORN BRANCH STREAM RESTORATION

# DETAILS

SEAL:

SEAL:

SEAL:

OF MAR

NAME OF MAR


OF M

D1 SCALE: AS SHOWN

BY: SF/NW CHECK: KT


DWG. NO.:


22 OF 34




MARYLAND DEPARTMENT OF ENVIRONMENT

WATER MANAGEMENT ADMINISTRATION







- PROTECTION AREA WILL BE SET AS PART OF THE REVIEW PROCESS
- BOUNDARIES OF PROTECTION AREA SHOULD BE STAKED AND FLAGGED PRIOR TO INSTALLING DEVICES.
- DEVICE SHOULD BE MAINTAINED THROUGHOUT CONSTRUCTION.

## **BLAZE ORANGE FENCE**

REBAR) AT LEAST 6 INCHES DEEP OVER THE LENGTH AND WIDTH OF THE SCE.

DIRECTED TO AN APPROVED SEDIMENT CONTROL PRACTICE.

U.S. DEPARTMENT OF AGRICULTURE

NATURAL RESOURCES CONSERVATION SERVICE

MAINTAIN ENTRANCE IN A CONDITION THAT MINIMIZES TRACKING OF SEDIMENT. ADD STONE OR MAKE

ROADWAY TO REMOVE MUD TRACKED ONTO PAVEMENT IS NOT ACCEPTABLE UNLESS WASH WATER IS

MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL

OTHER REPAIRS AS CONDITIONS DEMAND TO MAINTAIN CLEAN SURFACE. MOUNTABLE BERM. AND

SPECIFIED DIMENSIONS. IMMEDIATELY REMOVE STONE AND/OR SEDIMENT SPILLED, DROPPED, OR TRACKED ONTO ADJACENT ROADWAY BY VACUUMING, SCRAPING, AND/OR SWEEPING. WASHING

NOT TO SCALE

TAMPING TO SECURE THE MAT END IN THE KEY.

U.S. DEPARTMENT OF AGRICULTURE IATURAL RESOURCES CONSERVATION SERVICE


2 FOOT (MAXIMUM) CENTERS ALONG SEAMS, JOINTS, AND ROLL ENDS

8. STAPLE/STAKE MAT IN A STAGGERED PATTERN ON 4 FOOT (MAXIMUM) CENTERS THROUGHOUT AND

MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL

). ESTABLISH AND MAINTAIN VEGETATION SO THAT REQUIREMENTS FOR ADEQUATE VEGETATIVE

ESTABLISHMENT ARE CONTINUOUSLY MET IN ACCORDANCE WITH SECTION B-4 VEGETATIVE



- ACCESS ROUTES TO BE VERIFIED BY ENGINEER AT EROSION AND SEDIMENT CONTROL MEETING. REVISIONS TO THE ALIGNMENT THAT MINIMIZE TREE DISTURBANCE ARE ENCOURAGED AND REQUIRE REVIEW AND APPROVAL BY THE ENGINEER
- CONTRACTOR SHALL MAINTAIN MULCH ACCESS PATH THROUGHOUT THE CONSTRUCTION PERIOD. UPON COMPLETION OF PROJECT, ALL MULCH ACCESS ROADS SHALL BE REMOVED AND RESTORED TO PRE-EXISTING CONDITIONS.
- SCARIFICATION OF COMPACTED MULCH TO OCCUR UPON REMOVAL OF ACCESS ROAD, AT THE DIRECTION OF THE ENGINEER.

# **MULCH ACCESS ROAD**


MARYLAND DEPARTMENT OF ENVIRONMENT

STANDARD SYMBOL

TSSMS 2.0 lb/ft2

(\* INCLUDE SHEAR STRESS)

NOT TO SCALE



# CLIENT

6958 AVIATION BLVD., SUITE C GLEN BURNIE. MD 21061

301.850.0448

ISSUES / REVISIONS SUBMISSION DESCTRIPTION



The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

# **BUCKHORN BRANCH** STREAM RESTORATION

**EROSION AND** SEDIMENT CONTROL DETAILS

23006.01

SCALE: NTS BY: SF/NW

23 OF 34

 $\frac{2}{7}/2025 \quad \text{I:} \\ \text{Projects} \\ 23006.01 \quad \text{Buckhorn Branch Stream Restoration} \\ \text{CAD} \\ \text{Plans} \\ \text{dt01bb.dwg}$ 

#### MGWC 1.2: PUMP-AROUND PRACTICE

Temporary measure for dewatering inchannel construction sites

#### DESCRIPTION

The work should consist of installing a temporary pump around and supporting measures to divert flow around instream construction sites.

#### IMPLEMENTATION SEQUENCE

Sediment control measures, pump-around practices, and associated channel and bank construction should be completed in the following sequence (refer to Detail 1.2):

- Construction activities including the installation of erosion and sediment control measures should not begin
  until all necessary easements and/or right-of-ways have been acquired. All existing utilities should be marked
  in the field prior to construction. The contractor is responsible for any damage to existing utilities that may
  result from construction and should repair the damage at his/her own expense to the county's or utility
  company's satisfaction.
- 2. The contractor should notify the Maryland Department of the Environment or WMA sediment control inspector at least 5 days before beginning construction. Additionally, the contractor should inform the local environmental protection and resource management inspection and enforcement division and the provider of local utilities a minimum of 48 hours before starting construction.
- 3. The contractor should conduct a pre-construction meeting on site with the WMA sediment control inspector, the county project manager, and the engineer to review limits of disturbance, erosion and sediment control requirements, and the sequence of construction. The contractor should stake out all limits of disturbance prior to the pre-construction meeting so they may be reviewed. The participants will also designate the contractor's staging areas and flag all trees within the limit of disturbance which will be removed for construction access. Trees should not be removed within the limit of disturbance without approval from the WMA or local authority.
- 4. Construction should not begin until all sediment and erosion control measures have been installed and approved by the engineer and the sediment control inspector. The contractor should stay within the limits of the disturbance as shown on the plans and minimize disturbance within the work area whenever possible.
- 5. Upon installation of all sediment control measures and approval by the sediment control inspector and the local environmental protection and resource management inspection and enforcement division, the contractor should begin work at the upstream section and proceed downstream beginning with the establishment of stabilized construction entrances. In some cases, work may begin downstream if appropriate. The sequence of construction must be followed unless the contractor gets written approval for deviations from the WMA or local authority. The contractor should only begin work in an area which can be completed by the end of the day including grading adjacent to the channel. At the end of each work day, the work area must be stabilized and the pump around removed from the channel. Work should not be conducted in the channel during rain events.
- 6. Sandbag dikes should be situated at the upstream and downstream ends of the work area as shown on the plans, and stream flow should be pumped around the work area. The pump should discharge onto a stable velocity dissipater made of riprap or sandbags.

TEMPORARY INSTREAM CONSTRUCTION MEASURES

MARYLAND DEPARTMENT OF THE ENVIRONMENT

WATERWAY CONSTRUCTION GUIDELINES

REVISED NOVEMBER 2000

PAGE 1.2 - 1

1.2 - 1

# TREE PROTECTION FENCE TO BE ERECTED IN LINE WITH ROOT PRUNING TRENCH, FENCE, TRENCH, AND LOD ARE THE SAME LINE, SEE SEPARATE DETAIL FOR FENCE SPECIFICATIONS ROOT PRUNE TRENCH 24" MIN DEPTH OR AS DETERMINED AT PRECONSTRUTION MEETING

#### NOTES:

- 1. RETENTION AREAS WILL BE SET AS PART OF THE REVIEW PROCESS AND PRECONSTRUCTION MEETING.
- 2. BOUNDARIES OF RETENTION AREAS MUST BE STAKED AT THE PRECONSTRUCTION MEETING AND FLAGGED PRIOR TO TRENCHING.
- 3. EXACT LOCATION OF TRENCH SHALL BE DETERMINED IN THE FIELD IN COORDINATION WITH THE FOREST CONSERVATION (FC) INPECTOR .
- 4. TRENCH SHOULD BE IMMEDIATELY BACKFILLED WITH EXCAVATED SOIL OR OTHER ORGANIC SOIL AS SPECIFIED PER PLAN OR BY THE FC INSPECTOR.
- 5. ROOTS SHALL BE CLEANLY CUT USING VIBRATORY KNIFE OR OTHER ACCEPTABLE EQUIPMENT.
- 6. ALL PRUNING MUST BE EXECUTED WITH LOD SHOWN ON PLANS OR AS AUTHORIZED IN WRITING BY THE FC INSPECTOR.

#### **ROOT PRUNING DETAIL**

TREE SAVE AREA

NTS

#### MGWC 1.2: PUMP-AROUND PRACTICE


- 7. Water from the work area should be pumped to a sediment filtering measure such as a dewatering basin, sediment bag, or other approved source. The measure should be located such that the water drains back into the channel below the downstream sandbag dike.
- 8. Traversing a channel reach with equipment within the work area where no work is proposed should be avoided. If equipment has to traverse such a reach for access to another area, then timber mats or similar measures should be used to minimize disturbance to the channel. Temporary stream crossings should be used only when necessary and only where noted on the plans or specified. (See Section 4, Stream Crossings, Maryland Guidelines to Waterway Construction).
- 9. All stream restoration measures should be installed as indicated by the plans and all banks graded in accordance with the grading plans and typical cross-sections. All grading must be stabilized at the end of each day with seed and mulch or seed and matting as specified on the plans.
- 10. After an area is completed and stabilized, the clean water dike should be removed. After the first sediment flush, a new clean water dike should be established upstream from the old sediment dike. Finally, upon establishment of a new sediment dike below the old one, the old sediment dike should be removed.
- 11. A pump around must be installed on any tributary or storm drain outfall which contributes baseflow to the work area. This should be accomplished by locating a sandbag dike at the downstream end of the tributary or storm drain outfall and pumping the stream flow around the work area. This water should discharge onto the same velocity dissipater used for the main stem pump around.
- 12. If a tributary is to be restored, construction should take place on the tributary before work on the main stem reaches the tributary confluence. Construction in the tributary, including pump around practices, should follow the same sequence as for the main stem of the river or stream. When construction on the tributary is completed, work on the main stem should resume. Water from the tributary should continue to be pumped around the work area in the main stem.
- 13. The contractor is responsible for providing access to and maintaining all erosion and sediment control devices until the sediment control inspector approves their removal.


PAGE 1.2 - 2

14. After construction, all disturbed areas should be regraded and revegetated as per the planting plan.

TEMPORARY INSTREAM CONSTRUCTION MEASURES

# Maryland's Guidelines To Waterway Construction DETAIL 1.2: PUMP-AROUND PRACTICE






4. REMOVE AND PROPERLY DISPOSE OF FILTER BAG UPON COMPLETION OF PUMPING OPERATIONS OR AFTER BAG HAS REACHED CAPACITY, WHICHEVER OCCURS FIRST. SPREAD THE DEWATERED SEDIMENT FROM THE BAG IN AN APPROVED UPLAND AREA AND STABILIZE WITH SEED AND MULCH BY THE END OF THE WORK DAY. RESTORE THE SURFACE AREA BENEATH THE BAG TO ORIGINAL CONDITION UPON REMOVAL OF THE DEVICE.

5. USE NONWOVEN GEOTEXTILE WITH DOUBLE STITCHED SEAMS USING HIGH STRENGTH THREAD. SIZE SLEEVE TO ACCOMMODATE A MAXIMUM 4 INCH DIAMETER PUMP DISCHARGE HOSE. THE BAG MUST BE MANUFACTURED FROM A NONWOVEN GEOTEXTILE THAT MEETS OR EXCEEDS MINIMUM AVERAGE ROLL VALUES (MARV) FOR THE FOLLOWING:

GRAB TENSILE	250 LB	ASTM D-4632
PUNCTURE		ASTM D-4833
FLOW RATE	70 GAL/MIN/FT <sup>2</sup>	ASTM D-4491
PERMITTIVITY (SEC-1)		ASTM D-4491
	70% STRENGTH @ 500 HOURS	ASTM D-4355
APPARENT OPENING SIZE (AOS)	0.15-0.18 MM	ASTM D-4751
SEAM STRENGTH	90%	ASTM D-4632

6. REPLACE FILTER BAG IF BAG CLOGS OR HAS RIPS, TEARS, OR PUNCTURES. DURING OPERATION KEEP CONNECTION BETWEEN PUMP HOSE AND FILTER BAG WATER TIGHT. REPLACE BEDDING IF IT BECOMES DISPLACED.

MARYLAND STANDARDS AND SPE	CIFICATIONS FOR SOIL ER	ROSION AND SEDIMENT CONTROL	
U.S. DEPARTMENT OF AGRICULTURE ATURAL RESOURCES CONSERVATION SERVICE	2011	MARYLAND DEPARTMENT OF ENVIRONMEN WATER MANAGEMENT ADMINISTRATION	• •



MARYLAND DEPARTMENT OF THE ENVIRONMENT

WATERWAY CONSTRUCTION GUIDELINES

REVISED NOVEMBER 2000



CLIENT

ISSUES / REVISIONS

SUBMISSION DESCTRIPTION

6958 AVIATION BLVD., SUITE C

GLEN BURNIE. MD 21061


301.850.0448

The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship


# BUCKHORN BRANCH STREAM RESTORATION

EROSION AND
SEDIMENT
CONTROL DETAILS



DWG. NO.:

SCALE: NTS




#### <u>NOTES</u>

- 1. PROTECTION MEASURES WILL BE SET AS PART OF THE REVIEW PROCESS.
- 2. TIE SUFFICIENT 2"X8"X12' BOARDS AROUND MAIN TRUNK OF TREE WITH ½" DIAMETER ROPE (FIBER OR NYLON) TO PROTECT ALL AREAS EXPOSED TO CONSTRUCTION.
- 3. INSTALL WIRE EYE BOLTS WITH MINIMUM INNER DIAMETER OF  $\frac{5}{8}$ " AND MINIMUM LENGTH OF 4" FIRMLY IN EACH PLANK WHERE FIBER OR NYLON ROPES CROSS OVER PLANKS.
- 4. WHERE SIGNIFICANT TREE BRANCHES EXIST WHICH PREVENT PLANK INSTALLATION, PLANKING SHALL EXTEND TO THE ELEVATION OF THE LOWEST BRANCH.

# TREE PLANKING

NOT TO SCALE



OPEN AREA TREE PROTECTION FENCE N.T.S.

# TREE PROTECTION

TREE PROTECTION/REMOVAL GENERAL NOTES:

- 1. THE PLANS IDENTIFY THE MINIMUM ANTICIPATED SURVEYED TREE TO BE REMOVED BASED ON DATA COLLECTED DURING ASSESSMENT AND DESIGN. ALL OTHER TREES NOT EXPLICITLY SHOWN FOR REMOVAL WITHIN THE LOD ARE ASSUMED TO BE POTENTIAL TREE SAVES. HOWEVER, SITE CONDITIONS CHANGES AND MODIFICATIONS TO ACCESS ROUTES WARRANT REVIEW AND MODIFICATION OF THIS BEFORE CONSTRUCTION BEGINS.
- 2. AT THE BEGINNING OF EACH PHASE OF WORK, CONTRACTOR SHALL MARK IN THE FIELD ALL DESIGNED TREE REMOVALS AND ON TREES THAT ARE POSSIBLE REMOVALS NEAR THE VICINITY OF THE LIMITS OF GRADING AND/OR CONSTRUCTION ACCESS USING A NON-PERMANENT METHOD (FLAGGING OR WASHABLE PAINT). ALL OTHER TREES WITHIN THE LOD SHALL NOT BE MARKED IN THE FIELD FOR REMOVAL AND SHALL BE CONSIDERED TREE SAVES.
- 3. CONTRACTOR SHALL REVIEW ALL TREE REMOVALS WITH MNCPPC AND DESIGNATED SPECIALIST TO OBTAIN CONCURRENCE BASED ON TREE HEALTH, CONDITION, SPECIES, OBSTRUCTION TO CONSTRUCTION ACCESS, CONFLICTS WITH GRADING AND NEED FOR SELECTIVE HARVESTING. FIELD ADJUSTMENTS TO CONSTRUCTION ACCESS AND WORK LIMITS MAY BE MADE AT THIS TIME WITH AGREEMENT BY ALL PARTIES AND REMOVAL MARKINGS ADJUSTED ACCORDINGLY. AT THIS TIME, TREE PROTECTION MEASURES (PLANKING, FENCING, AND/OR ROOT PROTECTION) FOR TREES TO REMAIN SHALL BE DEFINED. GROUPS TREES MAY BE GROUPED AS ONE PROTECTION
- 4. CONTRACTOR SHALL INSTALL AGREED UPON TREE PROTECTION MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL TREES, SHRUBS AND VEGETATION AS AGREED TO REMAIN. WHEN POSSIBLE, TREES SHALL BE PROTECTED AT THE DRIP LINE AND NO VEHICLE, MATERIAL OR EQUIPMENT SHALL BE STORED WITHIN THIS AREA UNLESS OTHERWISE NOTED.
- 5. PRIOR TO TREE REMOVAL, CONTRACTOR SHALL SALVAGE UNDERSTORY VEGETATION WITH THE LIMITS OF GRADING AND/OR CONSTRUCTION ACCESS.
- 6. ANY LIMB OR ROOT PRUNING NECESSARY TO PROTECTED TREES THAT MAY BE DAMAGED BY CONSTRUCTION ACCESS OR GRADING WILL BE DONE BY A LICENSED ARBORIST.
- 7. ALL TREE REMOVALS SHALL BE DONE IN A MANNER TO MAXIMIZE THEIR USAGE IN THE STRUCTURES (I.E., MAINTAIN SPECIFIED TRUNK LENGTHS & DIAMETERS, ROOT WADS, ETC.) AND TO MINIMIZE NEGATIVE IMPACTS TO RESIDUAL STANDING TREES, SHRUBS, AND WETLANDS. TREE FELLING TO BE DONE IN ACCORDANCE WITH OSHA LOGGING STANDARD, 29 CFR 1910.266.
- 8. TREE PROTECTION MEASURES SHALL BE MAINTAINED THROUGHOUT THE DURATION OF CONSTRUCTION.
- FOLLOWING CONSTRUCTION, ALL TREE PROTECTION MEASURES, FLAGGING AND METAL TREE TAGS SHALL BE REMOVED BY THE CONTRACTOR.

NOT TO SCALE

# CLIENT

RFS

6958 AVIATION BLVD., SUITE C GLEN BURNIE, MD 21061 301.850.0448

DATE: ISSUES / REVISIONS

DD/MM/YYYY SUBMISSION DESCTRIPTION



The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

# BUCKHORN BRANCH STREAM RESTORATION

# EROSION AND SEDIMENT CONTROL DETAILS

BY: SF/NW

25 OF 34

PROJECT NO.: 23006.01

SEAL:

OF MARY

NOT TO

#### **B-4 STANDARDS AND SPECIFICATIONS**

#### VEGETATIVE STABILIZATION

<u>Definition</u>

Using vegetation as cover to protect exposed soil from erosion.

<u>Purpose</u>

To promote the establishment of vegetation on exposed soil.

#### Conditions Where Practice Applies

On all disturbed areas not stabilized by other methods. This specification is divided into sections on incremental stabilization; soil preparation, soil amendments and topsoiling; seeding and mulching; temporary stabilization; and permanent stabilization.

#### Effects on Water Quality and Quantity

Stabilization practices are used to promote the establishment of vegetation on exposed soil. When soil is stabilized with vegetation, the soil is less likely to erode and more likely to allow infiltration of rainfall, thereby reducing sediment loads and runoff to downstream areas.

Planting vegetation in disturbed areas will have an effect on the water budget, especially on volumes and rates of runoff, infiltration, evaporation, transpiration, percolation, and groundwater recharge. Over time, vegetation will increase organic matter content and improve the water holding capacity of the soil and subsequent plant growth.

Vegetation will help reduce the movement of sediment, nutrients, and other chemicals carried by runoff to receiving waters. Plants will also help protect groundwater supplies by assimilating those substances present within the root zone.

#### Sediment control practices must remain in place during grading, seedbed preparation, seeding, mulching, and vegetative establishment.

#### Adequate Vegetative Establishment

Inspect seeded areas for vegetative establishment and make necessary repairs, replacements, and reseedings within the

- 1. Adequate vegetative stabilization requires 95 percent groundcover.
- 2. If an area has less than 40 percent groundcover, restabilize following the original recommendations for lime, fertilizer, seedbed preparation, and seeding.
- 3. If an area has between 40 and 94 percent groundcover, over-seed and fertilize using half of the rates originally specified.
- 4. Maintenance fertilizer rates for permanent seeding are shown in Table B.6.

#### **B-4-5 STANDARDS AND SPECIFICATIONS**

#### <u>FOR</u>

#### PERMANENT STABILIZATION

To stabilize disturbed soils with permanent vegetation.

#### <u>Purpose</u>

To use long-lived perennial grasses and legumes to establish permanent ground cover on disturbed soils.

#### Conditions Where Practice Applies

Exposed soils where ground cover is needed for 6 months or more.

#### <u>Criteria</u>

Seed Mixtures

- 1. General Use
- a. Select one or more of the species or mixtures listed in Table B.3 for the appropriate Plant Hardiness Zone (from Figure B.3) and based on the site condition or purpose found on Table B.2. Enter selected mixture(s), application rates, and seeding dates in the Permanent Seeding Summary. The Summary is to be placed on the plan.
- b. Additional planting specifications for exceptional sites such as shorelines, stream banks, or dunes or for special purposes such as wildlife or aesthetic treatment may be found in USDA-NRCS Technical Field Office Guide, Section 342 - Critical Area Planting.
- c. For sites having disturbed area over 5 acres, use and show the rates recommended by the soil
- d. For areas receiving low maintenance, apply urea form fertilizer (46-0-0) at 3 ½ pounds per 1000 square feet (150 pounds per acre) at the time of seeding in addition to the soil amendments shown in the Permanent Seeding Summary.
- Turfgrass Mixtures
- a. Areas where turfgrass may be desired include lawns, parks, playgrounds, and commercial sites which will receive a medium to high level of maintenance
- b. Select one or more of the species or mixtures listed below based on the site conditions or purpose. Enter selected mixture(s), application rates, and seeding dates in the Permanent Seeding Summary. The summary is to be placed on the plan.
- i. Kentucky Bluegrass: Full Sun Mixture: For use in areas that receive intensive management. Irrigation required in the areas of central Maryland and Eastern Shore. Recommended Certified Kentucky Bluegrass Cultivars Seeding Rate: 1.5 to 2.0 pounds per 1000 square feet. Choose a minimum of three Kentucky bluegrass cultivars with each ranging from 10 to 35 percent of the total mixture by weight.
- ii. Kentucky Bluegrass/Perennial Rye: Full Sun Mixture: For use in full sun areas where

#### **B-4-2 STANDARDS AND SPECIFICATIONS**

#### SOIL PREPARATION, TOPSOILING, AND SOIL AMENDMENTS

#### <u>Definition</u>

The process of preparing the soils to sustain adequate vegetative stabilization

<u>Purpose</u>

Conditions Where Practice Applies

To provide a suitable soil medium for vegetative growth

Where vegetative stabilization is to be established.

<u>Criteria</u>

#### A. Soil Preparation

- 1. Temporary Stabilization
- a. Seedbed preparation consists of loosening soil to a depth of 3 to 5 inches by means of suitable agricultural or construction equipment, such as disc harrows or chisel plows or rippers mounted on construction equipment. After the soil is loosened, it must not be rolled or dragged smooth but left in the roughened condition. Slopes 3:1 or flatter are to be tracked with ridges running parallel to the contour of the slope.
- b. Apply fertilizer and lime as prescribed on the plans.
- c. Incorporate lime and fertilizer into the top 3 to 5 inches of soil by disking or other suitable

#### 2. Permanent Stabilization

- a. A soil test is required for any earth disturbance of 5 acres or more. The minimum soil conditions required for permanent vegetative establishment are:
- i. Soil pH between 6.0 and 7.0.
- ii. Soluble salts less than 500 parts per million (ppm).
- iii. Soil contains less than 40 percent clay but enough fine grained material (greater than 30 percent silt plus clay) to provide the capacity to hold a moderate amount of moisture. An exception: if lovegrass will be planted, then a sandy soil (less than 30 percent silt plus clay) would be acceptable.
- iv. Soil contains 1.5 percent minimum organic matter by weight.
- v. Soil contains sufficient pore space to permit adequate root penetration.
- b. Application of amendments or topsoil is required if on-site soils do not meet the above conditions.
- c. Graded areas must be maintained in a true and even grade as specified on the approved plan, then scarified or otherwise loosened to a depth of 3 to 5 inches.

rapid establishment is necessary and when turf will receive medium to intensive management. Certified Perennial Ryegrass Cultivars/Certified Kentucky Bluegrass Seeding Rate: 2 pounds mixture per 1000 square feet. Choose a minimum of three Kentucky bluegrass cultivars with each ranging from 10 to 35 percent of the total mixture by weight.

- iii. Tall Fescue/Kentucky Bluegrass: Full Sun Mixture: For use in drought prone areas and/or for areas receiving low to medium management in full sun to medium shade. Recommended mixture includes; Certified Tall Fescue Cultivars 95 to 100 percent, Certified Kentucky Bluegrass Cultivars 0 to 5 percent. Seeding Rate: 5 to 8 pounds per 1000 square feet. One or more cultivars may be blended.
- iv. Kentucky Bluegrass/Fine Fescue: Shade Mixture: For use in areas with shade in Bluegrass lawns. For establishment in high quality, intensively managed turf area. Mixture includes; Certified Kentucky Bluegrass Cultivars 30 to 40 percent and Certified Fine Fescue and 60 to 70 percent. Seeding Rate: 1½ to 3 pounds per 1000 square feet.

#### Select turfgrass varieties from those listed in the most current University of Maryland Publication, Agronomy Memo #77, "Turfgrass Cultivar Recommendations for Maryland"

Choose certified material. Certified material is the best guarantee of cultivar purity. The certification program of the Maryland Department of Agriculture, Turf and Seed Section, provides a reliable means of consumer protection and assures a pure genetic line

#### c. Ideal Times of Seeding for Turf Grass Mixtures

Western MD: March 15 to June 1, August 1 to October 1 (Hardiness Zones: 5b, 6a)

Central MD: March 1 to May 15, August 15 to October 15 (Hardiness Zone: 6b)

Southern MD, Eastern Shore: March 1 to May 15, August 15 to October 15 (Hardiness Zones: 7a, 7b)

- d. Till areas to receive seed by disking or other approved methods to a depth of 2 to 4 inches, level and rake the areas to prepare a proper seedbed. Remove stones and debris over 1½ inches in diameter. The resulting seedbed must be in such condition that future mowing of grasses will pose no difficulty.
- e. If soil moisture is deficient, supply new seedings with adequate water for plant growth (½ to 1 inch every 3 to 4 days depending on soil texture) until they are firmly established. This is especially true when seedings are made late in the planting season, in abnormally dry or hot seasons, or on adverse sites.

#### **Permanent Seeding Summary**

		one (from Figur e (from Table B		]	Lime Rate						
No.	Species	Application Rate (lb/ac)	Seeding Dates	Seeding Depths	N	P <sub>2</sub> O <sub>5</sub>	$K_20$	Diffe Rate			
	DEER- TONGUE		45 pounds	90 lb/ac	90 lb/ac	2 tons/ac					
4	CREEPING RED FESCUE	20	3/1 - 5/15 8/1 - 10/15	½- ½ in	per acre		70	per acre (1.0 lb/	(2 lb/	(2 lb/	(90 lb/
	VIRGINIA WILD RYE	5	3/1 - 5/15 8/1 - 10/15	½- ½ in	1000 sf)	1000 sf)	1000 sf)	1000 sf)			

#### d. Apply soil amendments as specified on the approved plan or as indicated by the results of a soil

e. Mix soil amendments into the top 3 to 5 inches of soil by disking or other suitable means. Rake lawn areas to smooth the surface, remove large objects like stones and branches, and ready the area for seed application. Loosen surface soil by dragging with a heavy chain or other equipment to roughen the surface where site conditions will not permit normal seedbed preparation. Track slopes 3:1 or flatter with tracked equipment leaving the soil in an irregular condition with ridges running parallel to the contour of the slope. Leave the top 1 to 3 inches of soil loose and friable. Seedbed loosening may be unnecessary on newly disturbed areas.

- 1. Topsoil is placed over prepared subsoil prior to establishment of permanent vegetation. The purpose is to provide a suitable soil medium for vegetative growth. Soils of concern have low moisture content, low nutrient levels, low pH, materials toxic to plants, and/or unacceptable soil gradation.
- 2. Topsoil salvaged from an existing site may be used provided it meets the standards as set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given soil type can be found in the representative soil profile section in the Soil Survey published by USDA-NRCS.
- 3. Topsoiling is limited to areas having 2:1 or flatter slopes where:
- a. The texture of the exposed subsoil/parent material is not adequate to produce vegetative growth.
- b. The soil material is so shallow that the rooting zone is not deep enough to support plants or furnish continuing supplies of moisture and plant nutrients.
- c. The original soil to be vegetated contains material toxic to plant growth.
- d. The soil is so acidic that treatment with limestone is not feasible 4. Areas having slopes steeper than 2:1 require special consideration and design.
- 5. Topsoil Specifications: Soil to be used as topsoil must meet the following criteria:
- a. Topsoil must be a loam, sandy loam, clay loam, silt loam, sandy clay loam, or loamy sand. Other soils may be used if recommended by an agronomist or soil scientist and approved by the appropriate approval authority. Topsoil must not be a mixture of contrasting textured subsoils and must contain less than 5 percent by volume of cinders, stones, slag, coarse fragments, gravel, sticks, roots, trash, or other materials larger than 1½ inches in diameter.
- b. Topsoil must be free of noxious plants or plant parts such as Bermuda grass, quack grass, Johnson grass, nut sedge, poison ivy, thistle, or others as specified.
- c. Topsoil substitutes or amendments, as recommended by a qualified agronomist or soil scientist and approved by the appropriate approval authority, may be used in lieu of natural topsoil.

#### 6. Topsoil Application

- a. Erosion and sediment control practices must be maintained when applying topsoil.
- b. Uniformly distribute topsoil in a 5 to 8 inch layer and lightly compact to a minimum thickness of 4 inches. Spreading is to be performed in such a manner that sodding or seeding can proceed with a minimum of additional soil preparation and tillage. Any irregularities in the surface resulting from topsoiling or other operations must be corrected in order to prevent the formation of depressions or water pockets.
- c. Topsoil must not be placed if the topsoil or subsoil is in a frozen or muddy condition, when the subsoil is excessively wet or in a condition that may otherwise be detrimental to proper grading

#### B. Sod: To provide quick cover on disturbed areas (2:1 grade or flatter).

#### General Specifications

- a. Class of turfgrass sod must be Maryland State Certified. Sod labels must be made available to the job foreman and inspector.
- b. Sod must be machine cut at a uniform soil thickness of 3/4 inch, plus or minus 1/4 inch, at the time of cutting. Measurement for thickness must exclude top growth and thatch. Broken pads and torn or uneven ends will not be acceptable.
- c. Standard size sections of sod must be strong enough to support their own weight and retain their size and shape when suspended vertically with a firm grasp on the upper 10 percent of the
- d. Sod must not be harvested or transplanted when moisture content (excessively dry or wet) may adversely affect its survival.
- e. Sod must be harvested, delivered, and installed within a period of 36 hours. Sod not transplanted within this period must be approved by an agronomist or soil scientist prior to its

#### Sod Installation

- a. During periods of excessively high temperature or in areas having dry subsoil, lightly irrigate the subsoil immediately prior to laying the sod.
- b. Lay the first row of sod in a straight line with subsequent rows placed parallel to it and tightly wedged against each other. Stagger lateral joints to promote more uniform growth and strength. Ensure that sod is not stretched or overlapped and that all joints are butted tight in order to prevent voids which would cause air drying of the roots.
- c. Wherever possible, lay sod with the long edges parallel to the contour and with staggering joints. Roll and tamp, peg or otherwise secure the sod to prevent slippage on slopes. Ensure solid contact exists between sod roots and the underlying soil surface.
- d. Water the sod immediately following rolling and tamping until the underside of the new sod pad and soil surface below the sod are thoroughly wet. Complete the operations of laying, tamping and irrigating for any piece of sod within eight hours.

#### 3. Sod Maintenance

- a. In the absence of adequate rainfall, water daily during the first week or as often and sufficiently as necessary to maintain moist soil to a depth of 4 inches. Water sod during the heat of the day
- b. After the first week, sod watering is required as necessary to maintain adequate moisture
- c. Do not mow until the sod is firmly rooted. No more than 1/3 of the grass leaf must be removed by the initial cutting or subsequent cuttings. Maintain a grass height of at least 3 inches unless otherwise specified.

#### and seedbed preparation.

disking or other suitable means.

- 1. Soil tests must be performed to determine the exact ratios and application rates for both lime and fertilizer on sites having disturbed areas of 5 acres or more. Soil analysis may be performed by a recognized private or commercial laboratory. Soil samples taken for engineering purposes may also be used for chemical analyses.
- 2. Fertilizers must be uniform in composition, free flowing and suitable for accurate application by
- mesh sieve and 98 to 100 percent will pass through a #20 mesh sieve.
- 5. Where the subsoil is either highly acidic or composed of heavy clays, spread ground limestone at the rate of 4 to 8 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil.

#### **B-4-4 STANDARDS AND SPECIFICATIONS**

#### **FOR** TEMPORARY STABILIZATION

<u>Definition</u> To stabilize disturbed soils with vegetation for up to 6 months.

#### <u>Purpose</u>

To use fast growing vegetation that provides cover on disturbed soils.

#### Conditions Where Practice Applies

Exposed soils where ground cover is needed for a period of 6 months or less. For longer duration of time, permanent stabilization practices are required.

#### <u>Criteria</u>

- 1. Select one or more of the species or seed mixtures listed in Table B.1 for the appropriate Plant Hardiness Zone (from Figure B.3), and enter them in the Temporary Seeding Summary below along with application rates, seeding dates and seeding depths. If this Summary is not put on the plan and completed, then Table B.1 plus fertilizer and lime rates must be put on the plan.
- 2. For sites having soil tests performed, use and show the recommended rates by the testing agency. Soil tests are not required for Temporary Seeding.
- 3. When stabilization is required outside of a seeding season, apply seed and mulch or straw mulch alone as prescribed in Section B-4-3.A.1.b and maintain until the next seeding season.

#### **Temporary Seeding Summary**

		ne (from Figure (from Table B.1	B.3): 6b	 SS/FOXTAIL MILLET	Fertilizer Rate	Lime Rate
No.	Species	Application Rate (lb/ac)	Seeding Dates	Seeding Depths	(10-20-20)	Inne ruic
	ANNUÂL RYEGRASS	40	3/1 - 5/15 8/1 - 10/15	0.5		
	FOXTAIL MILLET	30	5/16 - 7/31	0.5	436 lb/ac	2 tons/ac
					(10 lb/1000 sf)	(90 lb/1000 sf)
			,			

NOTE: IF PERMANENT STABILIZATION IS REQUIRED OUTSIDE OF SPECIFIED SEEDING DATES, THE CONTRACTOR SHALL PROVIDE TEMPORARY STABILIZATION MEASURES (SEED AND STRAW) UNTIL THE APPROPRIATE SEEDING DATES FOR THE SPECIFIED SEED MIXES OCCUR. THE CONTRACTOR SHALL PROVIDE PERMANENT STABILIZATION SEEDING WITHIN THE SPECIFIED SEEDING DATES.

#### Soil Amendments (Fertilizer and Lime Specifications)

- appropriate equipment. Manure may be substituted for fertilizer with prior approval from the appropriate approval authority. Fertilizers must all be delivered to the site fully labeled according to the applicable laws and must bear the name, trade name or trademark and warranty of the producer.
- 3. Lime materials must be ground limestone (hydrated or burnt lime may be substituted except when hydroseeding) which contains at least 50 percent total oxides (calcium oxide plus magnesium oxide). Limestone must be ground to such fineness that at least 50 percent will pass through a #100

4. Lime and fertilizer are to be evenly distributed and incorporated into the top 3 to 5 inches of soil by

CLIENT

ISSUES / REVISIONS

SUBMISSION DESCTRIPTION

6958 AVIATION BLVD., SUITE C

GLEN BURNIE, MD 21061

301.850.0448

The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com


Restore the Earth & Inspire Ecological Stewardship

# **BUCKHORN BRANCH** STREAM RESTORATION

**EROSION AND** SEDIMENT **CONTROL NOTES** 



BY: SF/NW





#### **Standard Erosion and Sediment Control Notes**

#### March 2024

- 1. The permittee shall notify the Department of Permitting Services (DPS) forty-eight (48) hours before commencing any land disturbing activity and, unless waived by the Department, shall be required to hold a pre-construction meeting between them or their representative, their engineer, and an authorized representative of the Department.
  - 2. The permittee must obtain inspection and approval by DPS at the following points:
    - A. At the required pre-construction meeting.
    - B. Following installation of sediment control measures and prior to any other land disturbing activity.
    - C. During the installation of a sediment basin or stormwater management structure at the required inspection points (see Inspection Checklist on plan). Notification prior to commencing construction is mandatory.
    - D. Prior to removal or modification of any sediment control structure(s).
    - E. Prior to final acceptance.
- 3. The permittee shall construct all erosion and sediment control measures per the approved plan and construction sequence, shall have them inspected and approved by the Department prior to beginning any other land disturbances, shall ensure that all runoff from disturbed areas is directed to the sediment control devices, and shall not remove any erosion or sediment control measure without prior permission from the Department.
- 4. The permittee shall protect all points of construction ingress and egress to prevent the deposition of materials onto traversed public thoroughfare(s). All materials deposited onto public thoroughfare(s) shall be removed immediately.
- 5. The permittee shall inspect periodically and maintain continuously in effective operating condition, all erosion and sediment control measures until such time as they are removed with prior permission from the Department. The permittee is responsible for immediately repairing or replacing any sediment control measures which have been damaged or removed by the permittee or any other person.
- 6. \* Following initial soil disturbance or re-disturbance, permanent or temporary stabilization must be completed within:
  - a) Three (3) calendar days as to the surface of all perimeter dikes, swales, ditches, perimeter slopes and all slopes steeper than 3 horizontal to 1 vertical (3:1); and

b) Seven (7) calendar days as to all other disturbed or graded areas on the project site not under active grading.

All areas disturbed outside of the perimeter sediment control system must be minimized and stabilized immediately. Maintenance must be performed as necessary to ensure continued stabilization.

- 7. The permittee shall apply \*sod, seed, and anchored straw mulch, or other approved stabilization measures to all disturbed areas within seven (7) calendar days after stripping and grading activities have ceased on that area. Maintenance shall be performed as necessary to ensure continued stabilization. Active construction areas such as borrow or stockpile areas, roadway improvements, and areas within fifty (50) feet of a building under construction may be exempt from this requirement, provided that erosion and sediment control measures are installed and maintained to protect those areas.
- 8. Prior to removal of sediment control measures, the permittee shall stabilize all contributory disturbed areas with required soil amendments and topsoil, using sod or an approved permanent seed mixture and an approved anchored mulch. Wood fiber mulch may only be used in seeding season when the slope does not exceed 10% and grading has been done to promote sheet flow drainage. Areas brought to finished grade during the seeding season shall be permanently stabilized within seven (7) calendar days of establishment. When property is brought to finished grade during the months of November through February, and permanent stabilization is found to be impractical, an approved temporary seed and straw anchored mulch shall be applied to disturbed areas. The final permanent stabilization of such property shall be completed prior to the following April 15.
- 9. The site permit, work, materials, approved SC/SM plans, and test reports shall be available at the site for inspection by duly authorized officials of Montgomery County.
- 10. Surface drainage flows over unstabilized cut and fill slopes shall be controlled by either preventing drainage flows from traversing the slopes or by installing mechanical devices to lower the water down slope without causing erosion. Dikes shall be installed and maintained at the top of cut or fill slopes until the slope and drainage area to it are fully stabilized, at which time they must be removed, and final grading done to promote sheet flow drainage. Mechanical devices must be provided at points of concentrated flow where erosion is likely to occur.
- 11. Permanent swales or other points of concentrated water flow shall be stabilized within 3 calendar days of establishment with \*sod or seed with an approved erosion control matting or by other approved stabilization measures.
- 12. Sediment control devices shall be removed, with permission of the Department, within thirty (30) calendar days following establishment of permanent stabilization in all contributory drainage areas. Stormwater management structures used temporarily for sediment control shall be converted to the permanent configuration within this time period as well.
- 13. \* No permanent cut or fill slope with a gradient steeper than 3:1 will be permitted in lawn maintenance areas or on residential lots. A slope gradient of up to 2:1 will be permitted in non-maintenance areas provided that those areas are indicated on the erosion and sediment control plan with a low-maintenance ground cover specified for permanent stabilization. Slope gradient steeper than 2:1 will not be permitted with vegetative stabilization.
- 14. The permittee shall install a splashblock at the bottom of each downspout unless the downspout is connected by a drain line to an acceptable outlet.

2

- 15. For finished grading, the permittee shall provide adequate gradients so as to prevent water from standing on the surface of lawns more than twenty-four (24) hours after the end of a rainfall, except in designated drainage courses and swale flow areas, which may drain as long as forty-eight (48) hours after the end of a rainfall.
- 16. Sediment traps or basins are not permitted within 20 feet of a building which is existing or under construction. No building may be constructed within 20 feet of a sediment trap or basin.
- All inlets in non-sump areas shall have asphalt berms installed at the time of base paving establishment.
- 18. The sediment control inspector has the option of requiring additional sediment control measures, as deemed necessary.
- 19. All trap elevations are relative to the outlet elevation, which must be on existing undisturbed ground.
- 20. \*Vegetative stabilization shall be performed in accordance with the Standards and Specifications for Soil Erosion and Sediment Control.
- 21. Sediment trap(s)/basin(s) shall be cleaned out and restored to the original dimensions when sediment has accumulated to the point of one-half (1/2) the wet storage depth of the trap/basin (1/4 the wet storage depth for ST-III) or when required by the sediment control inspector.
- 22. Sediment removed from traps/basins shall be placed and stabilized in approved areas, but not within a floodplain.
- 23. All sediment basins and traps must be surrounded with a welded wire safety fence. The fence must be at least 42 inches high, have posts spaced no farther apart than 8 feet, have mesh openings no greater the two inches in width and four inches in height, with a minimum of 14-gauge wire. Safety fence must be maintained in good condition at all times.
- 24. No excavation in the areas of existing utilities is permitted unless their location has been determined. Call "Miss Utility" at 1-800-257-7777, 48 hours prior to the start of work.
- 25. Off-site spoil or borrow areas must have prior approval by DPS.
- 26. Sediment trap/basin dewatering for cleanout or repair may only be done with the DPS inspector's permission. The inspector must approve the dewatering method for <u>each</u> application. The following methods may be considered:
  - A. Pump discharge may be directed to another on-site sediment trap or basin, provided it is of sufficient volume and the pump intake is floated to prevent agitation or suction of deposited sediments; or
  - B. the pump intake may utilize a Removable Pumping Station and must discharge into an undisturbed area through a non-erosive outlet; or
  - C. the pump intake may be floated and discharge into a Dirt Bag (12 oz. non-woven fabric), or approved equivalent, located in an undisturbed buffer area.

Remember: Dewatering operation and method <u>must</u> have prior approval by the DPS inspector.

3

- 27. The permittee must notify the Department of all utility construction activities within the permitted limits of disturbance prior to the commencement of those activities.
- 28. \* Topsoil must be applied to all pervious areas within the limits of disturbance prior to permanent stabilization in accordance with MDE "Standards and Specifications for Soil Preparation, Topsoiling, and Soil Amendments".

## CLIENT

RES

6958 AVIATION BLVD., SUITE C GLEN BURNIE, MD 21061 301.850.0448

DD/MM/YYYY SUBMISSION DESCTRIPTION

ISSUES / REVISIONS



The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

# BUCKHORN BRANCH STREAM RESTORATION

EROSION AND
SEDIMENT
CONTROL NOTES

PROJECT NO.: 23006.01

SEAL:

OF MARY

SEAL:

SEAL:

SEAL:

OF MARY

SEAL:

SEA

SCALE: AS SHOWN

BY: SF/NW

CHECK:

27 OF 34

<sup>\*</sup> Class of turfgrass sod must be Maryland State Certified. Sod labels must be made available to the job foreman and the Sediment Control Inspector.

#### STAGING AND STOCKPILE NOTES

DEFINITION - A MOUND OR PILE OF SOIL PROTECTED BY APPROPRIATELY DESIGNED EROSION AND SEDIMENT CONTROL MEASURES.

PURPOSE - TO PROVIDE A DESIGNATED LOCATION FOR THE TEMPORARY STORAGE OF SOIL THAT CONTROLS THE POTENTIAL FOR EROSION, SEDIMENTATION, AND CHANGES TO DRAINAGE PATTERNS. CONDITIONS WHERE PRACTICE APPLIES - STOCKPILE AREAS ARE UTILIZED WHEN IT IS NECESSARY TO SALVAGE AND STORE SOIL FOR LATER USE.

- 1. THE STOCKPILE LOCATION AND ALL RELATED SEDIMENT CONTROL PRACTICES MUST BE CLEARLY INDICATED ON THE EROSION AND SEDIMENT CONTROL PLAN.
- 2. THE FOOTPRINT OF THE STOCKPILE MUST BE SIZED TO ACCOMMODATE THE ANTICIPATED VOLUME OF MATERIAL AND BASED ON A SIDE SLOPE RATIO NO STEEPER THAN 2:1. BENCHING MUST BE PROVIDED IN ACCORDANCE WITH SECTION B-3 LAND GRADING.
- RUNOFF FROM THE STOCKPILE AREA MUST DRAIN TO A SUITABLE SEDIMENT CONTROL PRACTICE.
- ACCESS THE STOCKPILE AREA FROM THE UPGRADE SIDE.
- 5. CLEAR WATER RUNOFF INTO THE STOCKPILE AREA MUST BE MINIMIZED BY USE OF A DIVERSION DEVICE SUCH AS AN EARTH DIKE, TEMPORARY SWALE OR DIVERSION FENCE. PROVISIONS MUST BE MADE FOR DISCHARGING CONCENTRATED FLOW IN A NON-EROSIVE MANNER.
- 6. WHERE RUNOFF CONCENTRATES ALONG THE TOE OF THE STOCKPILE FILL, AN APPROPRIATE EROSION/SEDIMENT CONTROL PRACTICE MUST BE USED TO INTERCEPT THE DISCHARGE.
- 7. STOCKPILES MUST BE STABILIZED IN ACCORDANCE WITH THE 3/7 DAY STABILIZATION REQUIREMENT AS WELL AS STANDARD B-4-1 INCREMENTAL STABILIZATION AND STANDARD B-4-4 TEMPORARY STABILIZATION
- 8. IF THE STOCKPILE IS LOCATED ON AN IMPERVIOUS SURFACE, A LINER SHOULD BE PROVIDED BELOW THE STOCKPILE TO FACILITATE CLEANUP. STOCKPILES CONTAINING CONTAMINATED MATERIAL MUST BE COVERED WITH IMPERMEABLE SHEETING.

#### MAINTENANCE:

THE STOCKPILE AREA MUST CONTINUOUSLY MEET THE REQUIREMENTS FOR ADEQUATE VEGETATIVE ESTABLISHMENT IN ACCORDANCE WITH SECTION B-4 VEGETATIVE STABILIZATION. SIDE SLOPES MUST BE MAINTAINED AT NO STEEPER THAN A 2:1 RATIO. THE STOCKPILE AREA MUST BE KEPT FREE OF EROSION. IF THE VERTICAL HEIGHT OF A STOCKPILE EXCEEDS 20 FEET FOR 2:1 SLOPES, 30 FEET FOR 3:1 SLOPES, OR 40 FEET FOR 4:1 SLOPES, BENCHING MUST BE PROVIDED IN ACCORDANCE WITH SECTION B-3 LAND GRADING.

#### BEST MANAGEMENT PRACTICES FOR WORKING IN NONTIDAL WETLADS,

WETLAND BUFFERS, WATERWAYS, AND 100-YEAR FLOODPLAINS

- NO EXCESS FILL, CONSTRUCTION MATERIAL, OR DEBRIS SHALL BE STOCKPILED OR STORED IN NONTIDAL WETLANDS, NONTIDAL WETLAND BUFFERS, WATERWAYS, OR THE 100-YEAR FLOODPLIAN.
- PLACE MATERIALS IN A LOCATION AND MANNER WHICH DOES NOT ADVERSELY IMPACT SURFACE OR SUBSURFACE WATER FLOW INTO OR OUT OF NONTIDAL WETLANDS, NONTIDAL WETLAND BUFFERS, WATERWAYS, OR THE 100-YEAR FLOODPLAIN.
  - DO NOT USE THE EXCAVATED MATERIAL AS BACKFILL IF IT CONTAINS WASTE METAL PRODUCTS, UNSIGHTLY DEBRIS, TOXIC MATERIAL, OR ANY OTHER DELETERIOUS SUBSTANCE. IF ADDITIONAL BACKFILL IS REQUIRED, USE CLEAN MATERIAL FREE OF WASTE METAL PRODUCTS, UNSIGHTLY DEBRIS, TOXIC MATERIAL, OR ANY OTHER DELETERIOUS SUBSTANCE.
- PLACE HEAVY EQUIPMENT ON MATS OR SUITABLY OPERATE THE EQUIPMENT TO PREVENT DAMAGE TO NONTIDAL WETLANDS, NONTIDAL WETLAND BUFFERS, WATERWAYS, OR THE 100-YEAR FLOODPLAIN.
- REPAIR AND MAINTAIN ANY SERVICEABLE STRUCTURE OR FILL SO THERE IS NO PERMANENT LOSS OF NONTIDAL WETLANDS, NONTIDAL WETLAND BUFFERS, OR WATERWAYS, OR PERMANENT MODIFICATION OF THE 100-YEAR FLOODPLAIN IN EXCESS OF THAT LOST UNDER THE ORIGINALLY AUTHORIZED STRUCTURE OR FILL
- RECTIFY ANY NONTIDAL WETLANDS, WETLAND BUFFERS, WATERWAYS, OR 100-YEAR FLOODPLAIN TEMPORARILY IMPACTED BY ANY CONSTRUCTION.
- ALL STABILIZATION IN THE NONTIDAL WETLAND AND NONTIDAL WETLAND BUFFER SHALL CONSIST OF THE FOLLOWING SPECIES: ANNUAL RYEGRASS (LOLIUM MULTIFLORUM), MILLET (SETARIA ITALICA), BARLEY (HORDEUM SP.), OATS (UNIOLA SP.), AND/OR RYE (SECALE CEREALE). THESE SPECIES WILL ALLOW FOR THE STABILIZATION OF THE SITE WHILE ALSO ALLOWING FOR THE VOLUNTARY REVEGETATION OF NATURAL WETLAND SPECIES. OTHER NON-PERSISTENT VEGETATION MAY BE ACCEPTABLE, BUT MUST BE APPROVED BY THE NONTIDAL WETLANDS AND WATERWAYS DIVISION. KENTUCKY 31 FESCUE SHALL NOT BE UTILIZED IN WETLAND OR BUFFER AREAS. THE AREA SHOULD BE SEEDED AND MULCHED TO REDUCE EROSION AFTER CONSTRUCTION ACTIVITIES HAVE BEEN COMPLETED.
- AFTER INSTALLATION HAS BEEN COMPLETED, MAKE POST-CONSTRUCTION GRADES AND ELEVATIONS THE SAME AS THE ORIGINAL GRADES AND ELEVATIONS IN TEMPORARILY IMPACTED AREAS
- TO PROTECT AQUATIC SPECIES, IN-STREAM WORK IS PROHIBITED AS DETERMINED BY THE CLASSIFICATION OF THE STREAM:
  - USE I WATERS: IN-STREAM WORK SHALL NOT BE CONDUCTED DURING THE PERIOD MARCH 1 THROUGH JUNE 15, INCLUSIVE, DURING ANY YEAR.
  - USE III WATERS: IN-STREAM WORK SHALL NOT BE CONDUCTED DURING THE PERIOD OCTOBER 1 THROUGH APRIL 30, INCLUSIVE, DURING ANY YEAR.
  - USE IV WATERS: IN-STREAM WORK SHALL NOT BE CONDUCTED DURING THE PERIOD MARCH 1 THROUGH MAY 31, INCLUSIVE, DURING ANY YEAR.
- STORMWATER RUNOFF FROM IMPERVIOUS SURFACES SHALL BE CONTROLLED TO PREVENT THE WASHING OF DEBRIS INTO THE WATERWAY.
- CULVERTS SHALL BE CONSTRUCTED AND ANY RIPRAP PLACED SO AS NOT TO OBSTRUCT THE MOVEMENT OF AQUATIC SPECIES, UNLESS THE PURPOSE OF THE ACTIVITY IS TO IMPOUND WATER.

CLIENT

6958 AVIATION BLVD., SUITE C GLEN BURNIE. MD 21061

301.850.0448

ISSUES / REVISIONS SUBMISSION DESCTRIPTION



The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

# **BUCKHORN BRANCH** STREAM RESTORATION


**EROSION AND** SEDIMENT **CONTROL NOTES** 


23006.01


SCALE: AS SHOWN BY: SF/NW


28 OF 34


 $\frac{2}{7}/2025 \quad \text{I:} \\ \text{Projects} \\ 23006.01 \quad \text{Buckhorn Branch Stream Restoration} \\ \text{CAD} \\ \text{Plans} \\ \text{dt01bb.dwg}$ 












OMS - AN OVERALL MINIMUM SPACING DISTANCE \*OMS\* IS ASSIGNED TO THE PLANTING CONFIGURATION \*SEE PLANT SCHEDULE\*


AN INDIVIDUAL MINIMUM SPACING DISTANCES \*IMS\* IS ASSIGNED TO EACH INDIVIDUAL SPECIES \*SEE PLANT SCHEDULE\*

NOTE: EACH SYMBOL INDICATES A DIFFERENT SPECIES

#### PLANT SPACING - RANDOM




# SHRUB PLANTING - CONTAINER GROWN



# TREE PLANTING - CONTAINER GROWN

NOT TO SCALE



NOTES:

1. WELDED WIRE HERBIVORY PROTECTION CAGES TO BE INSTALLED AROUND ALL SHRUB CLUSTERS (SEE PLANTING PLAN).


- 3. CAGE SHALL BE FASTENED TO 2 X 2 IN. HARDWOOD GUYING STAKES, EACH WITH TWO (MIN.) 11-INCH RELEASABLE CABLE TIES (ONE AT TOP AND ONE 6 IN. (MIN.) ABOVE THE GROUND.
- 4. STAKES SHALL BE SPACED EVERY 8 FT. AROUND PERIMETER OF CAGE. 5. DO NOT DAMAGE PLANT MATERIAL DURING INSTALLATION.
- 6. CANOPY TREES MAY BE INSTALLED WITHIN CAGES.
- 7. CAGES TO BE REMOVED AT DIRECTION OF THE OWNER.
- 8. ENSURE CAGE IS SECURE TO GROUND TO PREVENT UPLIFT BY DEER
- WELDED WIRE HERBIVORY PROTECTION CAGE

# -NO. 14 GAUGE WIRE FABRIC WITH 2" x 4" OPENINGS. CREATE 2-FOOT DIAMETER CAGE AROUND TREE OR SHRUB AND FASTEN TO STAKE. 6' HARDWOOD GUYING STAKE (2' INTO GROUND), (1 STAKE PER TREE)

- DEER PROTECTION CAGES TO BE INSTALLED AROUND ALL PLANTED TREES.
- HEIGHT OF CAGE SHALL BE 4-FEET (MIN.)
- 3. CAGE SHALL BE FASTENED TO STAKE WITH TWO (MIN.) 11-INCH RELEASABLE CABLE TIES (ONE AT TOP AND ONE 6" (MIN.) ABOVE THE GROUND.)
- 4. DO NOT DAMAGE TREE DURING INSTALLATION.
- 5. DEER BARK PROTECTORS (ITEM #bg48, BY A.M. LEONARD, OR EQUAL) MAY BE SUBSTITUTED FOR TREES GREATER THAN 3/4" CALIPER. ALL OTHER SUBSTITUTIONS MUST BE APPROVED BY LANDSCAPE ARCHITECT
- 6. CAGES TO BE REMOVED AT DIRECTION OF FOREST ECOLOGIST.
- 7. ENSURE CAGE IS SECURE TO GROUND TO PREVENT UPLIFT BY DEER.

#### DEER PROTECTION CAGE

NOT TO SCALE



- 1. ALL TREES SHALL BE STAKED WITH TWO (2) 6'X2"X2" HARDWOOD STAKES AND SECURED WITH ARBOR TIE. DEER PROTECTION CAGES SHALL BE ADDED TO ALL STANDALONE TREES OUTSIDE OF BIORETENTION BOTTOM, SIDESLOPE, AND PERENNIAL MEADOW PLANTING ZONES.
- 2. HEIGHT OF DEER PROTECTION CAGE SHALL BE 4-FEET (MIN.)
- 3. CAGE SHALL BE FASTENED TO STAKES WITH TWO (MIN.)
- 11-INCH RELEASABLE CABLE TIES (ONE AT TOP AND ONE 6" (MIN.) ABOVE THE GROUND.
- 4. DO NOT DAMAGE TREE DURING INSTALLATION.
- 5. CAGES, ARBOR TIE AND STAKES TO BE REMOVED AT DIRECTION OF LANDSCAPE ARCHITECT.
- 6. ENSURE CAGE IS SECURE TO GROUND TO PREVENT UPLIFT.

# M-NCPPC TREE IMPACT MITIGATION AND ROW PLANTING STAKING AND DEER PROTECTION NOT TO SCALE

## CLIENT

6958 AVIATION BLVD.. SUITE C GLEN BURNIE, MD 21061 301.850.0448

ISSUES / REVISIONS SUBMISSION DESCTRIPTION



The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

**BUCKHORN BRANCH** STREAM RESTORATION

PLANTING DETAILS

23006.01

BY: SF/NW

SCALE: NTS

'ieam c	nt Floo	dplain Fore	est				S	ize (acres):	1.89
Overall Average Minimum Spacing (ft.)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Stratum/ Species Name <sup>1</sup>	Common Name	Unit	Spacing Type	Height	Individual Minimum Spacing (ft.)
15	194			TREES		•		•	•
		10	37	Betula nigra	River birch	CON (#7)	Random	6-8 ft.	47
		15	55	Carpinus caroliniana	American hornbeam	CON (#7)	Random	6-8 ft.	39
		5	18	Nyssa sylvatica	Black gum	CON (#7)	Random	6-8 ft.	68
		10	37	Platanus occidentalis	American sycamore	CON (#7)	Random	6-8 ft.	47
		20	73	Quercus alba	White oak	CON (#7)	Random	6-8 ft.	34
		20	73	Quecus bicolor	Swamp white oak	CON (#7)	Random	6-8 ft.	34
		10	37	Quercus michauxii	Swamp chestnut oak	CON (#7)	Random	6-8 ft.	47
		10	37	Quercus phellos	Willow oak	CON (#7)	Random	6-8 ft.	47
		100	367	= total					
8	681			SHRUBS					
		10	129	Hamamaelis virginiana	Witch hazel	CON (#3)	Clusters of $7^2$	18-36 in.	N/A
		15	193	Hydrangea arborescens	Smooth hydrangea	CON (#3)	Clusters of 7	18-36 in.	N/A
		15	193	llex verticillata	Winterberry	CON (#3)	Clusters of 7	18-36 in.	N/A
		15	193	Itea virginica	Virginia sweetspire	CON (#3)	Clusters of 7	18-36 in.	N/A
		20	257	Lindera benzoin	Spicebush	CON (#3)	Clusters of 7	18-36 in.	N/A
		15	193	Viburnum dentatum	Arrowwood	CON (#3)	Clusters of 7	18-36 in.	N/A
		10	129	Viburnum nudum	Smooth witherod	CON (#3)	Clusters of 7	18-36 in.	N/A
		100	1287	= total					
N/A	20			NATIVE SEED					
		100	38	Floodplain Mix - ERNMX - 15	4	LBS of P.L.S. 76 %	N/A	N/A	N/A
		100	38	= total					
N/A	30			COVER CROP SEED					
		100	57	Secale cereale	Grain rye	LBS of P.L.S. 76 %	N/A	N/A	N/A
		100	57	= total			<u> </u>		

<sup>1</sup>If species or material type (e.g. size, etc.) substitutions are necessary, consult with landscape architect prior to determinations.

<sup>2</sup>Plant species randomly in clusters of seven (7) at a 5-ft. o/c spacing between each individual shrub within clusters; canopy trees may be planted within clusters

CON = container; P.L.S. = pure live seed

PLANT CO	OMPOSITIO	N SCHEDULE							
Piedmo	ont Floo	dplain Fore	est Unde	erstory			s	ize (acres):	0.39
Overall Average Minimum Spacing (ft.)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Stratum/ Species Name <sup>1</sup>	Common Name	Unit	Spacing Type	Height	Individual Minimum Spacing (ft.)
8	681			SHRUBS					
		10	26	Hamamaelis virginiana	Witch hazel	CON (#3)	Clusters of 7 <sup>2</sup>	18-36 in.	N/A
		15	40	Hydrangea arborescens	Smooth hydrangea	CON (#3)	Clusters of 7	18-36 in.	N/A
		15	40	llex verticillata	Winterberry	CON (#3)	Clusters of 7	18-36 in.	N/A
		15	40	Itea virginica	Virginia sweetspire	CON (#3)	Clusters of 7	18-36 in.	N/A
		20	53	Lindera benzoin	Spicebush	CON (#3)	Clusters of 7	18-36 in.	N/A
		15	40	Viburnum dentatum	Arrowwood	CON (#3)	Clusters of 7	18-36 in.	N/A
		10	26	Viburnum nudum	Smooth witherod	CON (#3)	Clusters of 7	18-36 in.	N/A
		100	265	= total					
N/A	20			NATIVE SEED					
		100	8	Floodplain Mix - ERNMX - 154	4	LBS of P.L.S. 76 %	N/A	N/A	N/A
		100	8	= total					
N/A	30			COVER CROP SEED					
		100	12	Secale cereale	Grain rye	LBS of P.L.S. 76 %	N/A	N/A	N/A
		100	12	= total					

<sup>1</sup>If species or material type (e.g. size, etc.) substitutions are necessary, consult with landscape architect prior to determinations.

<sup>2</sup>Plant species randomly in clusters of seven (7) at a 5-ft. o/c spacing between each individual shrub within clusters; canopy trees may be planted within clusters

CON = container; P.L.S. = pure live seed

	Vegetation					_
Quantity	Stratum/	Common Name	Symbol	Unit	Spacing Type	Height <sup>2</sup>
	Species Name <sup>1</sup>					
	TREES					
2	Quercus alba	White oak	Qa	3-INCH CAL	See Plan	8-12 ft.
5	Quecus bicolor	Swamp white oak	Qb	3-INCH CAL	See Plan	8-12 ft.
3	Quecus coccinea	Scarlet oak	Qc	3-INCH CAL	See Plan	8-12 ft.
2	Quercus michauxii	Swamp chestnut oak	Qm	3-INCH CAL	See Plan	8-12 ft.
4	Quercus palustris	Pin oak	Qpa	3-INCH CAL	See Plan	8-12 ft.
3	Quercus phellos	Willow oak	Qph	3-INCH CAL	See Plan	8-12 ft.
2	Quercus rubra	Northern read oak	Qr	3-INCH CAL	See Plan	8-12 ft.
21	= total					

<sup>1</sup>If species or material type (e.g. size, etc.) substitutions are necessary, consult with landscape architect prior to determinations

<sup>2</sup>Specific heights may vary; range provided as general guideline

<sup>3</sup>All 3-inch CAL trees to be staked and encircled with a welded wire herbivory cage (see detail in plan set)

CAL = caliper

PLANT COMPOSITION SCHEDULE

#### **ROW Plantings** Stratum/ Common Name | Symbol | Spacing Type Height<sup>2</sup> Quantity Species Name<sup>1</sup> TREES Cercis canadensis Eastern redbud Cc Ov 1-INCH CAL 8-10 ft. Ostrya virginiana 1-INCH CAL 8-10 ft. See Plan 2 = total

NOTES:

<sup>1</sup>If species or material type (e.g. size, etc.) substitutions are necessary, consult with landscape architect prior to determinations

<sup>2</sup>Specific heights may vary; range provided as general guideline

<sup>3</sup>All 1-inch CAL trees to be staked and encircled with a welded wire herbivory cage (see detail in plan set)

CAL = caliper

PLANT C	OMPOSI	TION SCHE	DULE				_	
Live St	takes						Size (acres) <sup>2</sup> :	0.18
Overall Average Minimum Spacing (ft.)	Quantity per Acre	Frequency (%)	Species Quantity	Vegetation Strata/ Species Name <sup>1</sup>	Common Name	Unit	Spacing Type	Size (Diameter)
2	10890			LIVE STAKES				
		20	390	Alnus serrulata	Tag alder	36 in. live stake	Random	0.5" - 1.5"
		20	390	Cornus amomum	Silky dogwood	36 in. live stake	Random	0.5" - 1.5"
		20	390	Cornus sericea	Red-osier dogwood	36 in. live stake	Random	0.5" - 1.5"
		20	390	Salix nigra	Black willow	36 in. live stake	Random	0.5" - 1.5"
		20	390	Sambucus canadensis	Elderberry	36 in. live stake	Random	0.5" - 1.5"
		100	1950	= total				
NOTES:			_	_	_			

1. Use straw mulch in Turfgrass zone 2. Do not apply fertilizer in Turfgrass zone

<sup>1</sup>If species or material type (e.g. size, etc.) substitutions are necessary, consult with landscape architect prior to determinations.

<sup>2</sup>Live Staking area consists of an approximate 4-ft. wide zone beginning at the bottom of the stream bank extending up the banks toward the floodplain

on each side of the main stem channel excluding stream banks at riffle features

「urfgrass		Size	(acres):	0.08
Overall Minimum Spacing (ft.)	LBS per acre	Frequency (%)	Seed Quantity (LBS)	Turfgrass Seed Composition
N/A	Per SHA Section 705*	100	Per SHA Section 705*	Per SHA Section 920.06.07(a)*

CLIENT

6958 AVIATION BLVD., SUITE C GLEN BURNIE, MD 21061

301.850.0448

ISSUES / REVISIONS SUBMISSION DESCTRIPTION



The Stables Building 2081 Clipper Park Road Baltimore, MD 21211 / ph: 410.554.0156 fx: 410.554.0168 / www.biohabitats.com

Restore the Earth & Inspire Ecological Stewardship

# **BUCKHORN BRANCH** STREAM RESTORATION

# PLANTING SCHEDULES

23006.01

BY: SF/NW

SCALE: NTS